
PyS60 Library Reference

Release 1.3.23 final

19 June 2007

Nokia

Copyright © 2004-2007 Nokia Corporation.

This is Python for S60 version 1.3.23 final created by Nokia Corporation. Files added by Nokia Corporation are licensed under Apache License Version 2.0. The original software, including modifications of Nokia Corporation therein, is licensed under the applicable license(s) for Python 2.2.2, unless specifically indicated otherwise in the relevant source code file.

See <http://www.apache.org/licenses/LICENSE-2.0> and <http://www.python.org/2.2.2/license.html>

CONTENTS

1	Introduction	1
1.1	Scope	1
1.2	Audience	2
1.3	New in Release 1.3.23 final	2
1.4	Naming Conventions	2
2	API Summary	3
2.1	Python Standard Library	3
2.2	Python for S60 Extensions	3
2.3	Third-Party Extensions	4
3	Selected Issues on Python Programming for S60	5
3.1	Concurrency Aspects	5
3.2	Running Python for S60 Scripts	5
3.3	Standard I/O Streams	6
3.4	Usage of Unicode	6
3.5	Date and Time	6
3.6	Limitations of Thread Support	6
3.7	Scalable User Interface	7
3.8	Error Handling	7
3.9	Limitations and Areas of Development	7
4	Operating System Services and Information	9
4.1	e32 — A Symbian OS related services package	9
4.2	sysinfo — Access to system information	11
5	User Interface and Graphics	13
5.1	appuifw — Interface to the S60 GUI framework	13
5.2	graphics — A graphics related services package	27
5.3	camera — Interface for taking photographs	33
5.4	keycapture — Interface for global capturing of key events.	35
5.5	topwindow — Interface for creating windows that are shown on top of other applications.	36
5.6	gles — Bindings to OpenGL ES	38
5.7	glcanvas — UI Control for Displaying OpenGL ES Graphics	44
6	Audio and Communication Services	47
6.1	audio — An audio related services package	47
6.2	telephone — Telephone services	49
6.3	messaging — A messaging services package	49
6.4	inbox — Interface to device inbox	50
6.5	location — GSM location information	51
6.6	position — Simplified interface to the Location Acquisition API	52
7	Data Management	55

7.1	<code>contacts</code> — A contacts related services package	55
7.2	<code>calendar</code> — Access to calendar related services	60
7.3	<code>calendar for EKA2</code> — Access to calendar related services	65
7.4	<code>e32db</code> — Interface to the Symbian native DB	70
7.5	<code>e32dbm</code> — DBM implemented using the Symbian native DBMS	73
8	Standard Library Support and Extensions	75
8.1	Support for Python Standard Library	75
8.2	Extensions to Standard Library Modules	76
9	Extending and Embedding	79
9.1	Python/C API Extensions	79
9.2	Extending Python for S60	80
10	Terms and Abbreviations	83
A	Reporting Bugs	87
	Module Index	89
	Index	91

Introduction

The Python for S60 Platform (Python for S60) simplifies application development and provides a scripting solution for the Symbian C++ APIs. This document is for Python for S60 release 1.3.23 final that is based on Python 2.2.2.

The documentation for Python for S60 includes three documents:

- Getting Started with Python for S60 Platform [5] contains information on how to install Python for S60 and how to write your first program.
- This document contains API and other reference material.
- Programming with Python for S60 Platform [6] contains code examples and programming patterns for S60 devices that can be used as a basis for programs.

The Python for S60 as installed on a S60 device consists of:

- Python runtime package that consists of:
 - Python interpreter DLL
 - Standard and proprietary Python library modules
 - S60 UI application framework adaptation component (a DLL) that connects the scripting domain components to the S60 UI
- Python script shell package that consists of:
 - an application written in Python and visible in the application menu of the device that provides an execution environment for Python scripts.
 - For S60 platform versions prior to 3rd Edition: Python Installer program for installing Python files on the device, which consists of:
 - * A recognizer plug-in that recognizes .py, .pyc, .pyd and .pyo files as belonging to Python.
 - * Symbian application written in Python that handles the installation of recognized Python files into the script shell environment.

A plugin for the S60 C++ SDK is also available. This plugin makes it possible to run Python scripts in the S60 emulator environment and to compile Python extension modules (PYDs) for the emulator and the device.

The Python for S60 developer discussion board [9] on the Forum Nokia Web site is a useful resource for finding out information on specific topics concerning Python for S60. You are welcome to give feedback or ask questions about Python for S60 through this discussion board.

1.1 Scope

This document includes the information required by developers to create applications that use Python for S60, and some advice on extending the platform.

1.2 Audience

This guide is intended for developers looking to create programs that use the native features and resources of the S60 phones. The reader should be familiar with the Python programming language (<http://www.python.org/>) and the basics of using Python for S60 (see Getting Started with Python for S60 Platform [5]).

1.3 New in Release 1.3.23 final

This section lists the updates in this document since release 1.3.8.

- Section 5.4, `keycapture` module has been added.
- Section 5.5, `topwindow` module has been added.
- Section 7.3, `calendar` module for EKA2 has been added.
- Method `signal_strength` for Section 4.2, `sysinfo` module has been added.
- Method `say` for Section 6.1, `audio` module has been added.
- Section 5.6 and 5.7, `gles` and `glcanvas` modules for OpenGL ES have been added.
- Method `start_finder` for Section 5.3, `camera` module has been added.
- Method `layout` for Section 5, `appuifw` module has been added.
- Method `inactivity` for Section 4.1, `e32` module has been added.
- Method `mms_send` for Section 6.3, `messaging` module has been added.
- Methods for access point selection has been added to `extension` module.
- Section 6.6, `position` module has been added.

1.4 Naming Conventions

Most names of the type `ESomething` typically indicate a constant defined by the Symbian SDK. More information about these constants can be found in the Symbian SDK documentation.

API Summary

All built-in object types of the Python language are supported in the S60 environment. The rest of the programming interfaces are implemented by various library modules as summarized in this chapter.

2.1 Python Standard Library

Python for S60 platform distribution does not include all of the Python's standard and optional library modules to save storage space in the phone. Nevertheless, many of the excluded modules also work in the S60 Python environment without any modifications. Some modules are included in the SDK version but not installed in the phone. For a summary of supported library modules, see Chapter 8.

When Python, available at <http://www.python.org/>, is installed on a PC, the library modules are by default located in '`\Python22\Lib`' on Windows and in '`/usr/lib/python2.2`' on Linux. The Python library modules' APIs are documented in [1].

Python for S60 extends some standard modules. These extensions are described in this document, see Chapter 8.2.

2.2 Python for S60 Extensions

There are two kinds of native C++ extensions in the Python for S60 Platform: built-in extensions and dynamically loadable extensions.

2.2.1 Built-in extensions

There are two built-in extensions in the Python for S60 package:

- The `e32` extension module is built into the Python interpreter on Symbian OS, and implements interfaces to special Symbian OS Platform services that are not accessible via Python standard library modules.
- The `appuifw` module for Python for S60 Platform offers UI application framework related Python interfaces.

2.2.2 Dynamically loadable extensions

These dynamically loadable extension modules provide proprietary APIs to S60 Platform's services:

- `graphics`: see Chapter 5.2
- `e32db`: see Chapter 7.4
- `messaging`: see Chapter 6.3

- [inbox](#): see Chapter 6.4
- [location](#): see Chapter 6.5
- [sysinfo](#): see Chapter 4.2
- [camera](#): see Chapter 5.3
- [audio](#): see Chapter 6.1
- [telephone](#): see Chapter 6.2
- [calendar](#): see Chapter 7.2
- [contacts](#): see Chapter 7.1
- [keycapture](#): see Chapter 5.4
- [topwindow](#): see Chapter 5.5
- [gles](#): see Chapter 5.6
- [glcanvas](#): see Chapter 5.7

2.3 Third-Party Extensions

It is also possible to write your own Python extensions. S60 related extensions to Python/C API are described in Chapter 9.1. For some further guidelines on writing extensions in C/C++, see Chapter 9.2. In addition, for an example on porting a simple extension to S60, see [6].

Selected Issues on Python Programming for S60

The following issues must be considered when using Python on S60.

3.1 Concurrency Aspects

The thread that initializes the Python interpreter becomes the main Python thread. This is usually the main thread of a UI application. When an application written in Python launches, the Symbian platform infrastructure creates the main UI thread that starts the Python environment. If a Python program is started as a server with `e32.start_server`, then the Python main thread is not a UI thread.

It is possible to launch new threads via the services of `thread` module. Examples of such situations could be to overcome eventual problems with the fixed, relatively small stack size of the main UI application thread; or to perform some background processing while still keeping the UI responsive. These new threads are not allowed to directly manipulate the UI; in other words, they may not use the `appuifw` module.

Because of the limitations of the Python interpreter's final cleanup, Python applications on the Symbian OS should be designed in such a way that the main thread is the last thread alive.

A facility called active object is used extensively on the Symbian OS to implement co-operative, non-preemptive scheduling within operating system threads. This facility is also utilized with native APIs. A Python programmer is exposed to related concurrency issues particularly in UI programming. Preserving the responsiveness of the UI with the help of active objects needs to be considered when designing the application logic. At the same time it is necessary to take into account the resulting concurrent behavior within the application when active objects are used. While the main execution path of a UI script is blocked in wait for an active object to complete – either explicitly as a result of using `e32.Ao_lock`, or indirectly within some other Python API implementation – the UI-related callbacks may still get called.

The standard `thread.lock` cannot normally be used for synchronization in the UI application main thread, as it blocks the UI event handling that takes place in the same thread context. The Symbian active object based synchronization service called `e32.Ao_lock` has been implemented to overcome this problem. The main thread can wait in this lock, while the UI remains responsive.

Python for S60 tries to minimize the unwanted exposure of a Python programmer to the active objects of the Symbian OS. The programmer may choose to implement the eventual concurrent behavior of the application with normal threads. However, certain active object based facilities are offered as an option in the `e32` module.

3.2 Running Python for S60 Scripts

The current options for installing Python scripts to a S60 device are: a stand-alone installation to the device's main application menu, and an installation to a folder hierarchy maintained by the Python script

shell. For more details on this topic, see Programming with Python for S60 Platform [6]. In the first case the script application is launched via application menu, and it executes in its own process context. The latter case is suitable for development, testing, and trying out new scripts.

The Python script shell delivered with Python for S60 package has itself been written in Python. It is a collection of scripts that offer an interactive Python console and a possibility to execute scripts located in the directory of the script shell. Due to this kind of design the scripts are not fully isolated from each other. This means that any changes a script makes in the script shell namespace are visible to other scripts as well. This may be helpful during the development of a script suite, as long as care is taken to avoid unwanted interference between scripts.

For some special issues to consider when writing Python scripts to be run in the current Python script shell, see Programming with Python for S60 Platform [6]. These include the arrangements for standard output and the maintenance of the Options menu contents.

Note: Note that unlike some previous releases, the current version of the Python for S60 script shell takes care of restoring `appuifw.app.menu`, `appuifw.app.title`, `appuifw.app.exit_key_handler`, `appuifw.app.screen`, `appuifw.app.body`, `sys.stderr` and `??` after a script has been run, and The application programmer doesn't need to save and restore these settings.

3.3 Standard I/O Streams

The standard Python I/O streams in the `sys` module are by default connected to underlying C STDLIB's `stdio` streams that in turn are terminated by dummy file descriptors. Usually Python scripts set the I/O streams suitably by manipulating them at Python level via `sys` module interface. The `e32` extension module offers a Python interface for attaching to C STDLIB's output streams, but this service is only recommended for debugging purposes. The `e32._stdo` function takes as its argument the name of the file where C STDLIB's `stdout` and `stderr` are to be redirected. This makes it possible to capture the low-level error output when the Python interpreter has detected a fatal error and aborts.

3.4 Usage of Unicode

No changes have been made to the standard library modules with regard to string argument and return value types. S60 extensions generally accept both plain strings and Unicode strings as arguments, but they return only Unicode strings. APIs that take string arguments for the purpose of showing them on the UI expect Unicode strings. Giving something else may result in garbled appearance of the text on the screen.

3.5 Date and Time

Unix time, seconds since January 1, 1970, 00:00:00 UTC (Coordinated Universal Time), is generally used as the time format in the Python for S60 APIs described in this document. The float type is used for storing time values.

3.6 Limitations of Thread Support

Python for S60 supports starting native threads via the standard `thread` module. However, the native APIs Python for S60 uses have certain limitations that a Python programmer must be aware of.

Objects that wrap native resources can typically be used only in the thread they are created in. This is because native resources cannot be shared between native threads. Examples:

Note:

- Symbian OS STDLIB implementation has some limitations that are reflected at OS module support (see S60 SDK documentation [4]). For example, STDLIB file descriptors cannot be shared between threads, and for that reason, Python file objects cannot either.
- Sockets as implemented in the S60 version of the `socket` module.

Warning: Trying to use native objects from the wrong thread can crash the interpreter. If display of panic codes is enabled, a typical panic code displayed in this case is “KERN-EXEC 3”.

3.7 Scalable User Interface

Note: S60 2nd Edition FP3 and further releases.

S60 2nd Edition FP3 enables a new feature called scalable user interface. For Python developers this feature is currently visible in new APIs supporting the scalable UI, icon loading, and new screen resolutions. For more information on scalable user interface, see Section 5.1.8, Icon Type of this document, as well as Programming with Python for S60 Platform [6].

3.8 Error Handling

The APIs described in this document may raise any standard Python exceptions. In situations where a Symbian error code is returned, its symbolic name is given as the value parameter of a `SymbianError` exception.

In case where the functions have nothing special to return, they return `None` on success.

3.9 Limitations and Areas of Development

Some OS level concepts to which the standard `os` library module offers an interface do not exist as such in Symbian OS environment. An example of this is the concept of current working directory.

Reference cycle garbage collection is not in use. Because of this, special care needs to be taken to dismantle cyclic references when a Python program exits. This prevents error messages related to native resources that are left open. The problem could be removed by developing support for collection of cyclic garbage or by performing a special cleanup action on interpreter exit. The `gc` module has been ported to the Symbian OS, and it has been verified to work. However, the current distribution has been built without `gc` support.

Operating System Services and Information

4.1 e32 — A Symbian OS related services package

The `e32` module offers Symbian OS related utilities that are not related to the UI and are not provided by the standard Python library modules.

4.1.1 Module Level Functions

The following free functions - functions that do not belong to any class - are defined in the `e32` module:

`ao_yield()`

Yields to the active scheduler to have ready active objects with priority above normal scheduled for running. This has the effect of flushing the eventual pending UI events. Note that the UI callback code may be run in the context of the thread that performs an `ao_yield`. For information on active scheduler, see S60 SDK documentation [4].

`ao_sleep(interval [, callback])`

Sleeps for the given *interval* without blocking the active scheduler. When the optional *callback* is given, the call to `ao_sleep` returns immediately and the *callback* gets called after *interval*. See also Section 4.1.3, `Ao_timer` Type.

`ao_callgate(wrapped_callable)`

Wraps *wrapped_callable* into returned callable object *callgate* that can be called in any thread. As a result of a call to *callgate*, *wrapped_callable* gets called in the context of the thread that originally created the callgate. Arguments can be given to the call. This is actually a simple wrapping of the Symbian active object facility.

`drive_list()`

Returns a list of currently visible drives as a list of Unicode strings '`<driveletter>:`'

`file_copy(target_name, source_name)`

Copies the file *source_name* to *target_name*. The names must be complete paths.

`in_emulator()`

Returns 1 if running in an emulator, or 0 if running on a device.

`set_home_time(time)`

Set the device's time to *time* (see Section 3.5).

`pys60_version`

A string containing the version number of the Python for S60 and some additional information.

Example:

```
>>> import e32
>>> e32.pys60_version
'1.2 final'
```

`pys60_version_info`

A tuple containing the five components of the Python for S60 version number: major, minor, micro, release tag, and serial. All values except release level are integers; the release tag is a string. A value other than 'final' for the release tag signifies a development release. The `pys60_version_info` value corresponding to the Python for S60 version 1.2 is (1, 2, 0, 'final', 0).

`s60_version_info`

The SDK version with which this Python was compiled (tuple). The following values are possible:

- (1, 2) for S60 1st Edition
- (2, 0) for S60 2nd Edition
- (2, 6) S60 2nd Edition Feature Pack 2
- (2, 8) S60 2nd Edition Feature Pack 3
- (3, 0) S60 3rd Edition

Examples:

```
>>> import e32
>>> e32.pys60_version
'1.2.0 final'
>>> e32.pys60_version_info
(1, 2, 0, 'final', 0)
>>> e32.s60_version_info
(2, 0)
>>>
```

`is_ui_thread()`

Returns True if the code that calls this function runs in the context of the UI thread; otherwise returns False.

`start_exe(filename, command [,wait])`

Launches the native Symbian OS executable *filename* (Unicode) and passes it the *command* string. When *wait* is set, the function synchronously waits for the exit of the executable and returns a value that describes the exit type. Possible values are 0 for normal exit and 2 for abnormal exit.

`start_server(filename)`

Starts the Python script in file *filename* (Unicode) as a server in its own process. Note that `appuifw` module is not available to a server script.

`reset_inactivity()`

Resets the timers since the user was last active. As a consequence, the device backlight is normally turned on when this function is invoked.

`inactivity()`

Returns the time in seconds since the user of the device was last active.

4.1.2 Ao_lock Type

`class Ao_lock()`

Creates an `Ao_lock` instance. A Symbian active object based synchronization service. This can be used in the main thread without blocking the handling of UI events. The application should not exit while a thread is waiting in `Ao_lock`. If `Ao_lock.wait` is called while another `wait` call is already in progress, an `AssertionError` is raised.

Instances of `Ao_lock` type have the following methods:

`wait()`

If the lock has already been signaled, returns immediately. Otherwise blocks in wait for the lock to be signaled. Only one waiter is allowed, so you should avoid recursive calls to this service. `wait` can only be called in the thread that created the lock object. During the wait, other Symbian-active objects are being served, so the UI will not freeze. This may result in the UI callback code

being run in the context of the thread that is waiting in `Ao_lock`. This must be considered when designing the application logic.

`signal()`

Signals the lock. The waiter is released.

4.1.3 `Ao_timer` Type

The rationale for the `Ao_timer` type is that you cannot cancel a pending `e32.ao_sleep`. This is problematic if e.g. the user exits an application which is sleeping. In this case a panic would occur since the sleep is not cancelled - this is the reason you should avoid using `e32.ao_sleep` and instead use the `Ao_timer` with appropriate `cancel` calls if there is for example a possibility for the user to exit the application during a sleep.

`class Ao_timer()`

Creates an `Ao_timer` instance. A Symbian active object based sleeping service. This can be used in the main thread without blocking the handling of UI events. The application should not exit while a thread has a pending `after` call in `Ao_timer`. Only one `after` invocation can be pending at time for each instance of this type.

Instances of `Ao_timer` type have the following methods:

`after(interval [,callback])`

Sleeps for the given interval without blocking the active scheduler. When the optional callback is given, the call to `after` returns immediately and the callback gets called after interval.

`cancel()`

Cancels a pending `after` call.

4.2 `sysinfo` — Access to system information

The `sysinfo` module offers an API for checking the system information of a S60 mobile device.

Note: The method `ring_type` is not available for S60 1st Edition.

The `sysinfo` module has the following functions:

`active_profile()`

Returns the current active profile as a string, which can be one of the following: `'general'`, `'silent'`, `'meeting'`, `'outdoor'`, `'pager'`, `'offline'`, `'drive'`, or `'user <profile value>'`.

`battery()`

Returns the current battery level. On devices based on S60 2nd Edition Feature Pack 1 (S60 2.1) or earlier the value ranges from 0 (empty) to 7 (full). On newer devices the value ranges from 0 (empty) to 100 (full). On the emulator the value is always 0.

Note: The returned value may be incorrect while the device is being charged.

`display_twips()`

Returns the width and height of the display in twips. For a definition of a twip, see Chapter 10, Terms and Abbreviations.

`display_pixels()`

Returns the width and height of the display in pixels.

`free_drivespace()`

Returns the amount of free space left on the drives in bytes, for example `{u'C:' 100}`. The keys in the dictionary are the drive letters followed by a colon (:).

`imei()`

Returns the IMEI code of the device as a Unicode string or, if running on the emulator, the hardcoded string `u'0000000000000000'`.

`max_ramdrive_size()`

Returns the maximum size of the RAM drive on the device.

`total_ram()`

Returns the amount of RAM memory on the device.

`free_ram()`

Returns the amount of free RAM memory available on the device.

`total_rom()`

Returns the amount of read-only ROM memory on the device.

`ring_type()`

Not supported in 1st Edition! Returns the current ringing type as a string, which can be one of the following: 'normal', 'ascending', 'ring_once', 'beep', or 'silent'.

`os_version()`

Returns the operating system version number of the device as a three element tuple (major version, minor version, build number). The elements are as follows¹:

- The major version number, ranging from 0 to 127 inclusive
- The minor version number, ranging from 0 to 99 inclusive
- The build number, ranging from 0 to 32767 inclusive.

`signalBars()`

Returns the current network signal strength ranging from 0 to 7, with 0 meaning no signal and 7 meaning a strong signal. If using an emulator, value 0 is always returned.

`signal_dbm()`

Returns the current network signal strength in dBm. This is available SDK 2.8 onwards. If using an emulator value 0 is always returned.

`sw_version()`

Returns the software version as a Unicode string. On the emulator, returns the hardcoded string u'emulator'. For example, a software version can be returned as u'V 4.09.1 26-02-04 NHL-10 (c) NMP'.

¹Descriptions for these values are based on information found in S60 SDK documentation [4].

User Interface and Graphics

5.1 appuifw — Interface to the S60 GUI framework

The `appuifw` module offers an interface to the S60 UI application framework. Figure 5.1 provides an overview of the Python for S60 environment for UI application programming.

Note: The services of this interface may only be used in the context of the main thread, that is, the initial thread of a UI application script.

5.1.1 Basics of appuifw Module

Figure 5.2 shows the layout of a S60 application UI in the normal screen mode and a summary of how it relates to the services available at the `appuifw` API. For alternative layouts, see Figure 5.3.

The main application window may be set up to be occupied by a UI control.

A multi-view application can show the different views as tabs in the navigation pane and react as the users navigate between tabs.

Dialogs always take precedence over the usual UI controls and appear on top of them.

UI controls are implemented as Python types. These types are available:

- `Text`
- `Listbox`
- `Canvas`

UI controls appear on the screen as soon as an instance of the corresponding Python type is set to the body field (`app.body`) of the current application UI.

`Form` is a versatile dialog implemented as a type.

The `Content_handler` type facilitates interfacing to other UI applications and common high-level UI components. It is based on the notion that designated handlers can reduce UI application interaction to operations on MIME-type content.

The following dialogs are implemented as functions:

- `note`
- `query`
- `multi_query`
- `selection_list`
- `multi_selection_list`




Figure 5.1: Python for S60 UI environment overview




Figure 5.2: The different parts of the screen when using the 'normal' layout




Figure 5.3: UI layouts. left: 'normal', middle: 'large', right: 'full'

- `popup_menu`

A dialog becomes visible as soon as the corresponding Python function has been called. The function returns with the eventual user input or information on the cancellation of the dialog. `Form` is an exception; it is shown when its `execute` method is called.

5.1.2 Softkeys

The softkeys are managed by the underlying S60 Platform. When no dialog is visible, the right softkey is bound to application exit and the left one represents an Options menu. Python for S60 offers an interface for manipulating the menu and for binding the Exit key to a Python-callable object (see Section 5.1.4).

The native code that implements a dialog also manages the softkeys of the dialog, typically OK and Cancel. When the user input needs to be validated before accepting it and dismissing the dialog, it is best to use `Form`.

5.1.3 Module Level Functions

The following free functions - functions that do not belong to any class - are defined in the `appuifw` module:

`available_fonts()`

Returns a list (Unicode) of all fonts available in the device.

`query(label, type[, initial_value])`

Performs a query with a single-field dialog. The prompt is set to *label*, and the type of the dialog is defined by *type*. The value of *type* can be any of the following strings:

- 'text'
- 'code'
- 'number'
- 'date'
- 'time'
- 'query'
- 'float'

The type of the optional *initial_value* parameter and the returned input depend on the value of *type*:

- For text fields, ('text', 'code') it is Unicode
- For number fields, it is numeric
- For date fields, it is seconds since epoch rounded down to the nearest local midnight

A simple confirmation query and time query take no initial value and return `True/None` and seconds since local midnight, correspondingly. All queries return `None` if the users cancel the dialog.

For 'float' query the *initial_value* setting has no effect.

`multi_query(label_1, label_2)`

A two-field text (Unicode) input dialog. Returns the inputted values as a 2-tuple. Returns `None` if the users cancel the dialog.

`note(text[, type[, global]])`

Displays a note dialog of the chosen type with *text* (Unicode). The default value for *type* is 'info', which is automatically used if *type* is not set. *type* can be one of the following strings: 'error', 'info', or 'conf'.

If *global* (integer) is any other value than zero a global note is displayed. A global note is displayed even if the Python application calling this function is in background. The same set of *types* is supported as in standard note.

`popup_menu(list[, label])`

A pop-up menu style dialog. *list* representing the menu contents can be a list of Unicode strings or a list of Unicode string pairs (tuples). The resulting dialog list is then a single-style or a double-style list. A single-style list is shown in full; whereas a double-style list shows the items one at a time. Returns `None` if the user cancels the operation.

`selection_list(choices[, search_field=0])`

Executes a dialog that allows the users to select a list item and returns the *index* of the chosen item, or `None` if the selection is cancelled by the users. *choices* is a list of Unicode strings. *search_field* is 0 (disabled) by default and is optional. Setting it to 1 enables a search field (find pane) that facilitates searching for items in long lists. If enabled, the search field appears after you press a letter key.

`multi_selection_list(choices[, style='checkbox', search_field=0])`

Executes a dialog that allows the users to select multiple list items. Returns a tuple of indexes (a pair of Unicode strings) of the chosen items, or empty tuple if the selection is cancelled by the users. *choices* is a list of Unicode strings. *style* is an optional string; the default value being 'checkbox'. If 'checkbox' is given, the list will be a checkbox list, where empty checkboxes indicate what items can be marked. The other possible value that can be set for *style* is 'checkmark'. If 'checkmark' is given, the list will be a markable list, which lists items but does not indicate specifically that items can be selected. To select items on a markable list, use the Navigation key to browse the list and the Edit key to select an item. For example views on checkbox and markable lists, see Figure 5.4. *search_field* is 0 (disabled) by default and is optional. Setting it to 1 enables a search field (find pane) that facilitates searching for items in long lists. If enabled, the search field is always visible with checkbox lists; with markable lists it appears by pressing a letter key.

Example:

```
tuple = appuifw.multi_selection_list(L, style='checkmark', search_field=1)
```

5.1.4 Application Type

A single implicit instance of this type always exists when `appuifw` module is present and can be referred to with the name `app`. New instances cannot be created by a Python program.

class Application

Instances of `Application` type have the following attributes:



Figure 5.4: Examples of a checkbox list (left) and a markable list (right)

body

The UI control that is visible in the application's main window. Currently either `Text`, a `Listbox` object, `Canvas`, or `None`.

exit_key_handler

A callable object that is called when the user presses the Exit softkey. Setting `exit_key_handler` to `None` sets it back to the default value.

menu

This is a list of the following kinds of items:

- `(title, callback)` which creates a regular menu item
- `(title, ((title, callback)[...]))` which creates a submenu

title (Unicode) is the name of the item and *callback* the associated callable object. The maximum allowed number of items in a menu, or items in a submenu, or submenus in a menu is 30.

Example:

```
appuifw.app.menu = [(u"Item 1", item1),
                    (u"Submenu 1",
                     ((u"Subitem 1", subitem1),
                      (u"Subitem 2", subitem2)))]
```

screen

The screen area used by an application. See Figure 5.3 for example screens. The appearance of the application on the screen can be affected by setting one of the following values: `'normal'`, `'large'`, and `'full'`.

Examples:

```
appuifw.app.screen='normal' # (a normal screen with title pane and softkeys)
appuifw.app.screen='large'  # (only softkeys visible)
appuifw.app.screen='full'   # (a full screen)
```

title

The title the application that is visible in the application's title pane. Must be Unicode.

focus

A callable object that is called with integer as parameter (0 = focus lost, 1 = focus regained) when the application receives focus or it is switched to background. Focus is received e.g. when the application is switched from background to foreground or when the focus is regained from screensaver. Similarly when the screensaver is displayed, focus is lost.

Examples:

```
>>> import appuifw
>>> def cb(fg):
```

```

...     if(fg):
...         print "foreground"
...     else:
...         print "background"
...
>>> appuifw.app.focus=cb
>>> # switch to background, following text is printed from callback:
>>> background
>>> # switch to foreground, following text is printed from callback:
>>> foreground

```

Note: An improper callback can cause adverse effects. If you, for example, define a callback which takes no parameters you will receive never-ending `TypeError` exceptions on the Nokia 6600.

Instances of `Application` type have the following methods:

`activate_tab(index)`

Activates the tab *index* counting from zero.

`full_name()`

Returns the full name, in Unicode, of the native application in whose context the current Python interpreter session runs.

`uid()`

Returns the UID, in Unicode, of the native application in whose context the current Python interpreter session runs.

`set_exit()`

Requests a graceful exit from the application as soon as the current script execution returns.

`set_tabs(tab_texts[,callback=None])`

Sets tabs with given names on them in the navigation bar; *tab_texts* is a list of Unicode strings. When the users navigate between tabs, *callback* gets called with the index of the active tab as an argument. Tabs can be disabled by giving an empty or one-item *tab_texts* list.

`layout(layout_id)`

Note: Available from S60 2ndEd FP3 onwards (inclusive).

Returns as a tuple the size and the position of the requested *layout_id*. The logical layouts are outlined partly in Figure 5.2. The position is given from the top left corner. The *layout_id* can be one of the constants defined in module `appuifw`¹:

`EScreen`

Screen.

`EApplicationWindow`

Window that fills the entire screen.

`EStatusPane`

Indicates common components for most of the applications.

`EMainPane`

The application main pane is used in all the applications.

`EControlPane`

Control pane.

`ESignalPane`

The signal pane is used to indicate signal strength.

`EContextPane`

The context pane is used to indicate an active application.

`ETitlePane`

Used to indicate the subject or the name of the main pane content.

`EBatteryPane`

The battery pane is used to indicate battery strength.

¹Descriptions of the values are from the S60 SDK documentation [4].

EUniversalIndicatorPane

The universal indicator pane is used to indicate items that require the user's attention while browsing applications.

ENaviPane

The navi pane is used to indicate navigation within an application, to provide context sensitive information to the user while entering or editing data, or to show additional information.

EFindPane

A fixed find pane is used with lists instead of the find pop-up window.

EWallpaperPane

Wallpaper pane.

EIndicatorPane

The universal indicator pane is used to indicate items that require the user's attention while browsing applications.

EAColumn

Used generally to display small sized graphics or heading texts.

EBColumn

Used generally to display large sized icons or heading texts.

ECColumn

Used generally to display data entered by the user. Overlaps with the D column.

EDCcolumn

Used generally to display additional icons. Overlaps with the C column.

EStaconTop

Top part of status and control panes in landscape layout.

EStaconBottom

Bottom part of status and control panes in landscape layout.

EStatusPaneBottom

Bottom part of status pane in landscape layout.

EControlPaneBottom

Bottom part of control pane in landscape layout.

EControlPaneTop

Top part of control pane in landscape layout.

EStatusPaneTop

Top part of status pane in landscape layout.

Example:

```
>>> import appuifw
>>> appuifw.app.layout(appuifw.EMainPane)
((176, 144), (0, 44))
>>> # size and position (x, y) of the main pane in Nokia N70
```

5.1.5 Form Type

Form implements a dynamically configurable, editable multi-field dialog. **Form** caters for advanced dialog use cases with requirements such as free selectability of the combination of fields, possibility of validating the user input, and automatically producing the contents of some dialog fields before allowing the closing of the dialog.

```
class Form(fields[, flags=0])
```

Creates a **Form** instance. *fields* is a list of *field descriptors*: (*label*, *type*[, *value*]) where *label* is a Unicode string

type is one of the following strings: 'text', 'number', 'date', 'time', 'combo' or 'float'

value, depending on *type*: Unicode string, numeric, float (seconds since Unix epoch rounded down to the nearest local midnight), float (seconds since local midnight), ([*choice_label* ...], *index*) of float. For 'float' *type* the initial value setting might not be shown in the UI.

`Form` can also be configured and populated after construction. The configuration flags are visible as an attribute. `Form` implements the list protocol that can be used for setting the form fields, as well as obtaining their values after the dialog has been executed.

Instances of `Form` type have the following attributes:

`flags`

This attribute holds the values of the various configuration flags. Currently supported flags are:

`FFormEditModeOnly`

When this flag is set, the form remains in edit mode while `execute` runs.

`FFormViewModeOnly`

When this flag is set, the form cannot be edited at all.

`FFormAutoLabelEdit`

This flag enables support for allowing the end-users to edit the labels of the form fields.

`FFormAutoFormEdit`

This flag enables automatic support for allowing the end-users to add and delete the form fields. Note that this is an experimental feature and is not guaranteed to work with all SDK versions.

`FFormDoubleSpaced`

When this flag is set, double-spaced layout is applied when the form is executed: one field takes two lines, as the label and the value field are on different lines.

`menu`

A list of (`title`, `callback`) pairs, where each pair describes an item in the form's menu bar that is active while the dialog is being executed. `title` (Unicode) is the name of the item and `callback` the associated callable object.

`save_hook`

This attribute can be set to a callable object that receives one argument and returns a Boolean value. It gets called every time the users want to save the contents of an executing `Form` dialog. A candidate list for new form content - a list representing the currently visible state of the UI - is given as an argument. The list can be modified by `save_hook`. If `save_hook` returns `True`, the candidate list is set as the new contents of the form. Otherwise, the form UI is reset to reflect the field list contained in `Form` object.

Instances of `Form` type have the following methods:

`execute()`

Executes the dialog by making it visible on the UI.

`insert(index, field_descriptor)`

Inserts the field descriptor into the `Form` before the given `index`.

`pop()`

Removes the last field descriptor from the `Form` and returns it.

`length()`

the number of field descriptors in the form.

The subscript notation `f[i]` can be used to access or modify the *i*-th element of the form `f`. Same limitations as discussed above in the context of the flag `FFormAutoFormEdit` apply to modifying a form while it is executing. The ability to change the schema of a form while it is executing is an experimental feature.

5.1.6 Text Type

`Text` is a text editor UI control. For examples on the options available with `Text`, see Figure 5.5.

Instances of `Text` type have the following attributes:

`color`

The color of the text. `color` supports the same color representation models as the `graphics`



Figure 5.5: Examples of the options available for Text type

module. For the supported color representation models, see Section 5.2.

focus

A Boolean attribute that indicates the focus state of the control. Editor control also takes the ownership of the navigation bar, and this feature is needed to enable the usage of this control in applications that use the navigation bar - for example, navigation tabs.

font

The font of the text. There are two possible ways to set this attribute:

- Using a supported Unicode font, for example `u"Latin12"`. Trying to set a font which is not supported by the device has no effect. A list of supported fonts can be retrieved by using `appuifw.available_fonts`.

Example, setting font:

```
t = appuifw.Text()
t.font = u"albi17b" # sets font to Albi 17 bold
t.font = u"LatinPlain12" # sets font to Latin Plain 12
```

- Using one of the default device fonts that are associated with the following labels (plain strings): `'annotation'`, `'title'`, `'legend'`, `'symbol'`, `'dense'`, `'normal'` Example, setting font:

```
t.font = "title" # sets font to the one used in titles
```

Example, checking the currently set font:

```
unicodeFont = t.font
```

The attribute value retrieved is always a Unicode string. If the font has been set with a label, for example, `'title'`, the attribute will retrieve the font associated with that label.

highlight_color

The highlight color of the text. `highlight_color` supports the same color representation models as the `graphics` module. For the supported color representation models, see Section 5.2.

style

The style of the text. The flags for this attribute are defined in the `appuifw` module. These flags can be combined by using the binary operator `|`. The flags can be divided into two types: text style and text highlight. Text style flags can be freely combined with each other. However, one or more text style flags can be combined with only one text highlight flag. The flags are:

Text style:

`STYLE_BOLD`

Enables bold text.

`STYLE_UNDERLINE`
Enables underlined text.

`STYLE_ITALIC`
Enables italic text.

`STYLE_STRIKETHROUGH`
Enables strikethrough.

Text highlight:

`HIGHLIGHT_STANDARD`
Enables standard highlight.

`HIGHLIGHT_ROUNDED`
Enables rounded highlight.

`HIGHLIGHT_SHADOW`
Enables shadow highlight.

Only one highlight is allowed to be used at once. Therefore, it is possible to combine only one highlight with one or more text styles.

Examples:

```
t = appuifw.Text()

# These and other similar values and combinations are valid:
t.style = appuifw.STYLE_BOLD
t.style = appuifw.STYLE_UNDERLINE
t.style = appuifw.STYLE_ITALIC
t.style = appuifw.STYLE_STRIKETHROUGH
t.style = (appuifw.STYLE_BOLD|
          appuifw.STYLE_ITALIC|
          appuifw.STYLE_UNDERLINE)

# These values are valid:
t.style = appuifw.HIGHLIGHT_STANDARD
t.style = appuifw.HIGHLIGHT_ROUNDED
t.style = appuifw.HIGHLIGHT_SHADOW

# This combination is NOT valid:
# Invalid code, do not try!
t.style = (appuifw.HIGHLIGHT_SHADOW|appuifw.HIGHLIGHT_ROUNDED)
```

Instances of `Text` type have the following methods:

`add(text)`

Inserts the Unicode string *text* to the current cursor position.

`bind(event_code, callback)`

Binds the callable Python object *callback* to event *event_code*. The key codes are defined in the `key_codes` library module. The call `bind(event_code, None)` clears an existing binding. In the current implementation the event is always passed also to the underlying native UI control.

`clear()`

Clears the editor.

`delete([pos=0, length=len()])`

Deletes *length* characters of the text held by the editor control, starting from the position *pos*.

`get_pos()`

Returns the current cursor position.

`len()`

Returns the length of the text string held by the editor control.

`get([pos=0, length=len()])`

Retrieves *length* characters of the text held by the editor control, starting from the position *pos*.

`set(text)`

Sets the text content of the editor control to Unicode string *text*.

`set_pos(cursor_pos)`

Sets the cursor to *cursor_pos*.

5.1.7 Listbox Type



Figure 5.6: Listbox with icons

An instance of this UI control type is visible as a listbox, also known as a list in Symbian, that can be configured to be a single-line item or a double-item listbox. Figure 5.6 shows a single-line item Listbox with icons. For more information on the MBM and MIF formats, see Section 5.1.8.

class `Listbox(list, callback)`

Creates a `Listbox` instance. A callable object *callback* gets called when a listbox selection has been made. *list* defines the content of the listbox and can be one of the following:

- A normal (single-line item) listbox: a list of Unicode strings, for example `[unicode_string item1, unicode_string item2]`
- A double-item listbox: a two-element tuple of Unicode strings, for example `[(unicode_string item1, unicode_string item1description), (unicode_string item2, unicode_string item2description)]`
- A normal (single-line item) listbox with graphics: a two-element tuple consisting of a Unicode string and an `Icon` object, for example `[(unicode_string item1, icon1), (unicode_string item2, icon2)]`.
- A double-item listbox with graphics: a three-element tuple consisting of two Unicode strings and one `Icon` object, for example `[(unicode_string item1, unicode_string item1description, icon1), (unicode_string item2, unicode_string item2description, icon2)]`

Example: To produce a normal (single-line item) listbox with graphics:

```
icon1 = appuifw.Icon(u"z:\\system\\data\\avkon.mbm", 28, 29)
icon2 = appuifw.Icon(u"z:\\system\\data\\avkon.mbm", 40, 41)
entries = [(u"Signal", icon1),
           (u"Battery", icon2)]
lb = appuifw.Listbox(entries, lbox_observe)
```

Instances of `Listbox` type have the following methods:

bind(*event_code, callback*)

Binds the callable Python object *callback* to event *event_code*. The key codes are defined in the

`key_codes` library module. The call `bind(event_code, None)` clears an existing binding. In the current implementation the event is always passed also to the underlying native UI control.

`current()`

Returns the currently selected item's index in the `Listbox`.

`set_list(list[, current])`

Sets the `Listbox` content to a list of Unicode strings or a list of tuples of Unicode strings. The accepted structures of `list` are the same as in the `Listbox` constructor. The optional argument `current` is the index of the focused list item.

5.1.8 Icon Type

An instance of `Icon` type encapsulates an icon to be used together with a `Listbox` instance. Note that currently `Icon` can only be used with `Listbox` (see Section 5.1.7).

MBM is the native Symbian OS format used for pictures. It is a compressed file format where the files can contain several bitmaps and can be referred to by a number. An `.mbg` file is the header file usually associated with an `.mbm` file, which includes symbolic definitions for each bitmap in the file. For example, an `'avkon.mbm'` file has an associated index file called `'avkon.mbg'`, which is included in S60 SDKs. For more information on the MBM format and the bitmap converter tool, see [4] and search the topics with the key term "How to provide Icons"; this topic also points you to the Bitmap Converter tool that can be used for converting bitmaps into the MBM format.

S60 2nd Edition FP3 introduces a new format for icons called Multi-Image File (MIF). This format is very similar to the MBM format and also contains several compressed files. The files to be compressed should be in Scalable Vector Graphics Tiny (SVG-T) format. For more information on the SVG format, see Scalable Vector Graphics (SVG) 1.1 Specification [10].

class `Icon(filename, bitmap, bitmapMask)`

Creates an icon. `filename` is a Unicode file name and must include the whole path. Note that MBM and MIF (MIF only in S60 2nd Edition FP3) are the only file formats supported. `bitmap` and `bitmapMask` are integers that represent the index of the icon and icon mask inside that file respectively.

Example: The following builds an icon with the standard signal symbol:

```
icon = appuifw.Icon(u"z:\\system\\data\\avkon.mbm", 28, 29)
```

5.1.9 Content_handler Type

An instance of `Content_handler` handles data content by its MIME type.

class `Content_handler([callback])`

Creates a `Content_handler` instance. A `Content_handler` handles data content by its MIME type. The optional `callback` is called when the embedded handler application started with the `open` method finishes.

Instances of `Content_handler` type have the following methods:

`open(filename)`

Opens the file `filename` (Unicode) in its handler application if one has been registered for the particular MIME type. The handler application is embedded in the caller's thread. The call to this function returns immediately. When the handler application finishes, the `callback` that was given to the `Content_handler` constructor is called.

`open_standalone(filename)`

Opens the file `filename` (Unicode) in its handler application if one has been registered for the particular MIME type. The handler application is started in its own process. The call to this function returns immediately. Note that `callback` is not called for applications started with this method.

5.1.10 Canvas Type

Canvas is a UI control that provides a drawable area on the screen and support for handling raw key events. **Canvas** supports the standard drawing methods that are documented in Section 5.2.

```
class Canvas([redraw_callback=None, event_callback=None, resize_callback=None])
```

Constructs a **Canvas**. The optional parameters are callbacks that are called when specific events occur.

Note: Watch out for cyclic references here. For example, if the callbacks are methods of an object that holds a reference to the **Canvas**, a reference cycle is formed that must be broken at cleanup time or the **Canvas** will not be freed.

redraw_callback is called whenever a part of the **Canvas** has been obscured by something, is then revealed, and needs to be redrawn. This can typically happen, for example, when the user switches away from the Python application and back again, or after displaying a pop-up menu. The callback takes as its argument a four-element tuple that contains the top-left and the bottom-right corner of the area that needs to be redrawn. In many cases redrawing the whole **Canvas** is a reasonable option.

event_callback is called whenever a raw key event is received. There are three kinds of key events: **EEventKeyDown**, **EEventKey**, and **EEventKeyUp**. When a user presses a key down, events **EEventKeyDown** and **EEventKey** are generated. When the key is released, an **EEventKeyUp** event is generated.

The argument to the *event_callback* is a dictionary that contains the following data for key events:

- 'type': one of **EEventKeyDown**, **EEventKey**, or **EEventKeyUp**
- 'keycode': the keycode of the key
- 'scancode': the scancode of the key
- 'modifiers': the modifiers that apply to this key event

Each key on the keyboard has one or more scancodes and zero or more keycodes associated with it. A scancode represents the physical key itself and a keycode is the result of state-related operating system defined processing done on the key. For keys that correspond to a symbol in the current character set of the phone, the keycode is equal to the code of the corresponding symbol in that character set. For example, if you are using the Nokia Wireless Keyboard (SU-8W), pressing the key A will always produce the scancode 65 (ASCII code for an upper case A), but the keycode could be either 65 or 91 (ASCII code for a lower case A) depending on whether or not the Shift key is pressed or Caps Lock is active.

The `key_codes` module contains definitions for the keycodes and scancodes. See Figure 5.7 for the codes of the most common keys on the phone keypad.

Some keys are handled in a special way:

- A short press of the Edit key causes it to stay down, meaning that no **EEventKeyUp** event is sent. The event is only sent after a long press.
- Detecting presses of the Voice tags key or the Power key is not supported.
- If the right softkey is pressed, the `appuifw.app.exit_key_handler` callback is always executed.

There is no way to prevent the standard action of the Hang-up key, the Menu key, the Power key or the Voice tags key from taking place.

resize_callback is called when screen size is changed when the **Canvas** rect size has been changed. The callback takes as its argument a two-element tuple that contains the new clientRect width and height.

Instances of **Canvas** type have the following attribute:

size

A two-element tuple that contains the current width and height of the **Canvas** as integers.

Instances of **Canvas** type have the same standard drawing methods that are documented in Section 5.2.



Key	Keycode	Scancode
1.	EKeyLeftSoftkey	EScancodeLeftSoftkey
2.	EKeyYes	EScancodeYes
3.	EKeyMenu	EScancodeMenu
4.	EKey0...9	EScancode0...9
5.	EKeyStar	EScancodeStar
6.	EKeyLeftArrow	EScancodeLeftArrow
7.	EKeyUpArrow	EScancodeUpArrow
8.	EKeySelect	EScancodeSelect
9.	EKeyRightArrow	EScancodeRightArrow
10.	EKeyDownArrow	EScancodeDownArrow
11.	EKeyRightSoftkey	EScancodeRightSoftkey
12.	EKeyNo	EScancodeNo
13.	EKeyBackspace	EScancodeBackspace
14.	EKeyEdit	EScancodeEdit
15.	EKeyHash	EScancodeHash

Figure 5.7: Keycodes and scancodes for phone keys usable from Python applications

5.2 graphics — A graphics related services package

The `graphics` module provides access to the graphics primitives and image loading, saving, resizing, and transformation capabilities provided by the Symbian OS.

The module is usable from both graphical Python applications and background Python processes. However, background processes have some restrictions, namely that plain string symbolic font names are not supported in background processes since background processes have no access to the UI framework (see also Section 5.2.4).

For an example on using this module, see [6].

Functions `Image.open` and `Image.inspect` and `Image` object methods `load`, `save`, `resize`, and `transpose` are not available for S60 1st Edition.

5.2.1 Module Level Functions

The following free functions - functions that do not belong to any class - are defined in the `graphics` module:

`screenshot()`

Takes a screen shot and returns the image in `Image` format.

5.2.2 Image Class Static Methods

The following `Image` class static methods are defined in the `graphics` module:

`Image.new(size[, mode='RGB16'])`

Creates and returns a new `Image` object with the given size and mode. *size* is a two-element tuple. *mode* specifies the color mode of the `Image` to be created. It can be one of the following:

- '1': Black and white (1 bit per pixel)
- 'L': 256 gray shades (8 bits per pixel)
- 'RGB12': 4096 colors (12 bits per pixel)
- 'RGB16': 65536 colors (16 bits per pixel)
- 'RGB': 16.7 million colors (24 bits per pixel)

`Image.open(filename)`

Note: Not supported in S60 1st Edition!

Returns a new `Image` object (mode `RGB16`) that contains the contents of the named file. The supported file formats are JPEG and PNG. The file format is automatically detected based on file contents. *filename* should be a full path name.

`Image.inspect(filename)`

Note: Not supported in S60 1st Edition!

Examines the given file and returns a dictionary of the attributes of the file. At present the dictionary contains only the image size in pixels as a two-element tuple, indexed by key 'size'. *filename* should be a full path name.

5.2.3 Image Objects

An `Image` object encapsulates an in-memory bitmap.

Note on asynchronous methods: Methods `resize`, `transpose`, `save`, and `load` have an optional callback argument. If the callback is not given, the method call is synchronous; when the method returns, the operation is complete or an exception has been raised. If the callback is given, the method calls are asynchronous. If all parameters are valid and the operation can start, the method call will return

immediately. The actual computation then proceeds in the background. When it is finished, the callback is called with an error code as the argument. If the given code is 0, the operation completed without errors, otherwise an error occurred.

It is legal to use an unfinished image as a source in a blit operation; this will use the image data as it is at the moment the blit is made and may thus show an incomplete result.

Image objects have the following methods:

`resize(newsize[, callback=None, keepaspect=0])`

Note: Not supported in S60 1st Edition!

Returns a new image that contains a resized copy of this image. If *keepaspect* is set to 1, the resize will maintain the aspect ratio of the image, otherwise the new image will be exactly the given size.

If *callback* is given, the operation is asynchronous, and the returned image will be only partially complete until *callback* is called.

`transpose(direction[, callback=None])`

Note: Not supported in S60 1st Edition!

Creates a new image that contains a transformed copy of this image. The *direction* parameter can be one of the following:

- **FLIP_LEFT_RIGHT:** Flips the image horizontally, exchanging left and right edges.
- **FLIP_TOP_BOTTOM:** Flips the image vertically, exchanging top and bottom edges.
- **ROTATE_90:** Rotates the image 90 degrees counterclockwise.
- **ROTATE_180:** Rotates the image 180 degrees.
- **ROTATE_270:** Rotates the image 270 degrees counterclockwise.

If *callback* is given, the operation is asynchronous and the returned image will be only partially complete until *callback* is called.

`load(filename[, callback=None])`

Note: Not supported in S60 1st Edition!

Replaces the contents of this **Image** with the contents of the named file, while keeping the current image mode. This **Image** object must be of the same size as the file to be loaded.

If *callback* is given, the operation is asynchronous and the loaded image will be only partially complete until *callback* is called. *filename* should be a full path name.

`save(filename[, callback=None, format=None, quality=75, bpp=24, compression='default'])`

Note: Not supported in S60 1st Edition!

Saves the image into the given file. The supported formats are JPEG and PNG. If *format* is not given or is set to **None**, the format is determined based on the file name extension: `'.jpg'` or `'.jpeg'` are interpreted to be in JPEG format and `'.png'` to be in PNG format. *filename* should be a full path name.

When saving in JPEG format, the *quality* argument specifies the quality to be used and can range from 1 to 100.

When saving in PNG format, the *bpp* argument specifies how many bits per pixel the resulting file should have, and *compression* specifies the compression level to be used.

Valid values for *bpp* are:

- **1:** Black and white, 1 bit per pixel
- **8:** 256 gray shades, 8 bits per pixel
- **24:** 16.7 million colors, 24 bits per pixel

Valid values for *compression* are:

- **'best':** The highest possible compression ratio, the slowest speed

- `'fast'`: The fastest possible saving, moderate compression
- `'no'`: No compression, very large file size
- `'default'`: Default compression, a compromise between file size and speed

If *callback* is given, the operation is asynchronous. When the saving is complete, the *callback* is called with the result code.

`stop()`

Stops the current asynchronous operation, if any. If an asynchronous call is not in progress, this method has no effect.

`Image` objects have the following attribute:

`size`

A two-element tuple that contains the size of the `Image`. Read-only.

5.2.4 Common Features of Drawable Objects

Objects that represent a surface that can be drawn on support a set of common drawing methods, described in this section. At present there are two such objects: `Canvas` from the `appuifw` module and `Image` from the `graphics` module.

Options

Many of these methods support a set of standard options. This set of options is as follows:

- *outline*: The color to be used for drawing outlines of primitives and text. If `None`, the outlines of primitives are not drawn.
- *fill*: The color to be used for filling the insides of primitives. If `None`, the insides of primitives are not drawn. If *pattern* is also specified, *fill* specifies the color to be used for areas where the pattern is white.
- *width*: The line width to be used for drawing the outlines of primitives.
- *pattern*: Specifies the pattern to be used for filling the insides of primitives. If given, this must be either `None` or a 1-bit (black and white) `Image`.

Coordinate representation

The methods accept an ordered set of coordinates in the form of a coordinate sequence. Coordinates can be of type `int`, `long`, or `float`. A valid coordinate sequence is a non-empty sequence of either

- Alternating x and y coordinates. In this case the sequence length must be even, or
- Sequences of two elements, that specify x and y coordinates.

Examples of valid coordinate sequences:

- `(1, 221L, 3, 4, 5.85, -3)`: A sequence of three coordinates
- `[(1,221L), (3,4), [5.12,6]]`: A sequence of three coordinates
- `(1,5)`: A sequence of one coordinate
- `[(1,5)]`: A sequence of one coordinate
- `[[1,5]]`: A sequence of one coordinate

Examples of invalid coordinate sequences:

Invalid code, do not use!

- `[]`: An empty sequence
- `(1,2,3)`: Odd number of elements in a flat sequence
- `[(1,2),(3,4),None]`: Contains an invalid element
- `([1,2],3,4)`: Mixing the flat and nested form is not allowed

Color representation

All methods that take color arguments accept the following two color representations:

- A three-element tuple of integers in the range from 0 to 255 inclusive, representing the red, green, and blue components of the color.
- An integer of the form `0xrrggbb`, where `rr` is the red, `gg` the green, and `bb` the blue component of the color.

For 12 and 16 bit color modes the color component values are simply truncated to the lower bit depth. For the 8-bit grayscale mode images the color is converted into grayscale using the formula $(2*r+5*g+b)/8$, rounded down to the nearest integer. For 1-bit black and white mode images the color is converted into black (0) or white (1) using the formula $(2*r+5*g+b)/1024$.

Examples of valid colors:

- `0xffff00`: Bright yellow
- `0x004000`: Dark green
- `(255,0,0)`: Bright red
- `0`: Black
- `255`: Bright blue
- `(128,128,128)`: Medium gray

Examples of invalid colors:

Invalid code, do not use!

- `(0,0.5,0.9)`: Floats are not supported
- `'#ff80c0'`: The HTML color format is not supported
- `(-1,0,1000)`: Out-of-range values
- `(1,2)`: The sequence is too short
- `[128,128,192]`: This is not a tuple

Font specifications

A font can be specified in three ways:

- None, meaning the default font
- a Unicode string that represents a full font name, such as `u'LatinBold19'`
- a plain string symbolic name that refers to a font setting currently specified by the UI framework
- as a two or three element tuple, where
 - the first element is the font name (unicode or string) or None for default font
 - the second element is the font height in pixels or None for default size
 - the third (optional) element is the flags applied to the font or None for default options.

The flags are the following:

- `FONT_BOLD` bold
- `FONT_ITALIC` italic
- `FONT_SUBSCRIPT` subscript
- `FONT_SUPERSCRIPT` superscript
- `FONT_ANTI_ALIAS` forces the font to be antialiased
- `FONT_NO_ANTI_ALIAS` forces the font to not be antialiased

You can combine the flags with the binary or operator “`|`”. For example, the flags setting `FONT_BOLD|FONT_ITALIC` will produce text that is both bold and italic.

Note: Antialiasing support is only available for scalable fonts.

You can obtain a list of all available fonts with the `appuifw` module function `available_fonts`.

The symbolic names for UI fonts are:

- `'normal'`
- `'dense'`
- `'title'`
- `'symbol'`
- `'legend'`
- `'annotation'`

Since background processes have no access to the UI framework, these symbolic names are not supported in them. You need to specify the full font name.

Common Methods of Drawable Objects

`line(coordseq[, <options>])`

Draws a line connecting the points in the given coordinate sequence. For more information about the choices available for *options*, see Section 5.2.4.

`polygon(coordseq[, <options>])`

Draws a line connecting the points in the given coordinate sequence, and additionally draws an extra line connecting the first and the last point in the sequence. If a fill color or pattern is specified, the polygon is filled with that color or pattern. For more information about the choices available for *options*, see Section 5.2.4.

`rectangle(coordseq[, <options>])`

Draws rectangles between pairs of coordinates in the given sequence. The coordinates specify the top-left and the bottom-right corners of the rectangle. The sequence must have an even number of coordinates. For more information about the choices available for *options*, see Section 5.2.4.

`ellipse(coordseq[, <options>])`

Draws ellipses between pairs of coordinates in the given sequence. The coordinates specify the top-left and bottom-right corners of the rectangle inside which the ellipse is contained. The sequence must have an even number of coordinates. For more information about the choices available for *options*, see Section 5.2.4.

`pieslice(coordseq, start, end[, <options>])`

Draws pie slices contained in ellipses between pairs of coordinates in the given sequence. The start and end parameters are floats that specify the start and end points of pie slice as the starting and ending angle in radians. The angle 0 is to the right, the angle $\pi/2$ is straight up, π is to the left and $-\pi/2$ is straight down. *coordseq* is interpreted the same way as for the `ellipse` method. For more information about the choices available for *options*, see Section 5.2.4.

`arc(coordseq, start, end[, <options>])`

Draws arcs contained in ellipses between pairs of coordinates in the given sequence. The start and end parameters are floats that specify the start and end points of pie slice as the starting and ending angle in radians. The angle 0 is to the right, the angle $\pi/2$ is straight up, π is to the left and $-\pi/2$ is straight down. *coordseq* is interpreted the same way as for the `ellipse` method. For more information about the choices available for *options*, see Section 5.2.4.

`point(coordseq[, <options>])`

Draws points in each coordinate in the given coordinate sequence. If the *width* option is set to greater than 1, draws a crude approximation of a circle filled with the outline color in the locations. Note that the approximation is not very accurate for large widths; use the `ellipse` method if you need a precisely formed circle. For more information about the choices available for *options*, see Section 5.2.4.

`clear([color=0xffffffff])`

Sets the entire surface of the drawable to the given color, white by default.

`text(coordseq, text[fill=0, font=None])`

Draws the given text in the points in the given coordinate sequence with the given color (default value is black) and the given font. The font specification format is described above.

`measure_text(text[font=None, maxwidth=-1, maxadvance=-1])`

Measures the size of the given text when drawn using the given font. Optionally you can specify the maximum width of the text or the maximum amount the graphics cursor is allowed to move (both in pixels).

Returns a tuple of three values:

- the bounding box for the text as a 4-tuple: (topleft-x, topleft-y, bottomright-x, bottomright-y)
- the number of pixels the graphics cursor would move to the right
- the number of characters of the text that fits into the given maximum width and advance

`blit(image[, target=(0,0), source=((0,0), image.size), mask=None, scale=0])`

Copies the source area from the given *image* to the target area in this drawable. The source area is copied in its entirety if *mask* is not given or is set to `None`. If the mask is given, the source area is copied where the mask is white. *mask* can be either `None`, a 1-bit (black and white) `Image` or (on S60 2nd edition FP2 and later) a grayscale `Image`, and must be of the same size as the source image. A grayscale mask acts as an alpha channel, i.e. partial transparency.

target and *source* specify the target area in this image and the source area in the given source. They are coordinate sequences of one or two coordinates. If they specify one coordinate, it is interpreted as the upper-left corner for the area; if they specify two coordinates, they are interpreted as the top-left and bottom-right corners of the area.

If *scale* is other than zero, scaling is performed on the fly while copying the source area to the

target area. If *scale* is zero, no scaling is performed, and the size of the copied area is clipped to the smaller of source and target areas.

Note that a `blit` operation with scaling is slower than one without scaling. If you need to blit the same `Image` many times in a scaled form, consider making a temporary `Image` of the scaling result and blitting it without scaling. Note also that the scaling performed by the `blit` operation is much faster but of worse quality than the one done by the `resize` method, since the `blit` method does not perform any antialiasing.

5.3 camera — Interface for taking photographs

Note: Not available for S60 1st Edition.

The `camera` module enables taking photographs.

The `camera` module has the following functions²:

`cameras_available()`

Returns the number of cameras available in the device.

`image_modes()`

Returns the image modes supported in the device as a list of strings, for example: `['RGB12', 'RGB', 'JPEG_Exif', 'RGB16']`.

`image_sizes()`

Returns the image sizes (resolution) supported in the device as a list of (x, y) tuples, for example: `[(640, 480), (160, 120)]`.

`flash_modes()`

Returns the flash modes available in the device as a list of strings.

`max_zoom()`

Returns the maximum digital zoom value supported in the device as an integer.

`exposure_modes()`

Returns the exposure settings supported in the device as a list of strings.

`white_balance_modes()`

Returns the white balance modes available in the device as a list of strings.

`take_photo([mode, size, flash, zoom, exposure, white_balance, position])`

Takes a photograph and returns the image in:

1. `Image` format (for more information on `Image` format, see Chapter 5.2 `graphics` Module) or
2. Raw JPEG data³.

The settings listed below describe all settings that are supported by the `camera` module. You can retrieve the mode settings available for your device by using the appropriate functions listed at the beginning of this chapter.

• *mode* is the display mode of the image. The default value is `'RGB16'`. The following display modes are supported for the `Image` format pictures taken:

- `'RGB12'`: 4096 colors (12 bits per pixel)
- `'RGB16'`: 65536 colors (16 bits per pixel). Default value, always supported
- `'RGB'`: 16.7 million colors (24 bits per pixel)

For the JPEG data format images the following modes are supported:

- `'JPEG_Exif'`: JPEG Exchangeable image file format
- `'JPEG_JFIF'`: JPEG File Interchange Format

²Descriptions for some of the values are based on information found in S60 SDK documentation [4]

³For more information, see e.g. <http://en.wikipedia.org/wiki/JPEG>.

Note that there is variety between the devices and the supported formats.

- *size* is the resolution of the image. The default value is (640, 480). The following sizes are supported, for example, in Nokia 6630: (1280, 960), (640, 480) and (160, 120).

- *flash* is the flash mode setting. The default value is 'none'. The following flash mode settings are supported:

- 'none'
No flash. Default value, always supported
- 'auto'
Flash will automatically fire when required
- 'forced'
Flash will always fire
- 'fill_in'
Reduced flash for general lighting
- 'red_eye_reduce'
Red-eye reduction mode

- *zoom* is the digital zoom factor. It is assumed to be on a linear scale from 0 to the maximum zoom value allowed in the device. The default value is 0, meaning that zoom is not used.

- *exposure* is the exposure adjustment of the device. Exposure is a combination of lens aperture and shutter speed used in taking a photograph. The default value is 'auto'. The following exposure modes are supported:

- 'auto'
Sets exposure automatically. Default value, always supported
- 'night'
Night-time setting for long exposures
- 'backlight'
Backlight setting for bright backgrounds
- 'center'
Centered mode for ignoring surroundings

- *white_balance* can be used to adjust white balance to match the main source of light. The term white balance refers to the color temperature of the current light. A digital camera requires a reference point to represent white. It will then calculate all the other colors based on this white point. The default value for *white_balance* is 'auto' and the following white balance modes are supported:

- 'auto'
Sets white balance automatically. Default value, always supported
- 'daylight'
Sets white balance to normal daylight
- 'cloudy'
Sets white balance to overcast daylight
- 'tungsten'
Sets white balance to tungsten filament lighting
- 'fluorescent'
Sets white balance to fluorescent tube lighting
- 'flash'
Sets white balance to flash lighting

- *position* is the camera used if the device, such as Nokia 6680, has several cameras. In Nokia 6680, the camera pointing to the user of the device is located in position 1, whereas the one pointing away from the user is located in position 0. The default *position* is 0.

If some other application is using the camera, this operation fails, with error `SymbianError: KErrInUse`. Invoking this function right after the device boot, might result in `SymbianError: KErrNotReady` error.

`start_finder(callable[, backlight_on=1, size=main_pane_size])`

Starts the camera viewfinder and binds a callback to receive `Image` format feed. When a new viewfinder frame is ready the callback is invoked with the `Image` as parameter.

The optional parameter `backlight_on` determines whether the device backlight is kept on when the camera view finder is in operation. By default, the backlight is on (1 = on, 0 = off).

The optional parameter `size` (of type tuple, e.g. (176, 144)) can be used to change the size of the `Image` received in the callback. The default `size` is the same as the application's main pane size.

Example view finder code:

```
>>> import appuifw
>>> import camera
>>> def cb(im):
...     appuifw.app.body.blit(im)
...
>>> import graphics
>>> appuifw.app.body=appuifw.Canvas()
>>> camera.start_finder(cb)
>>>
```

`stop_finder()`

Stops the viewfinder.

`release()`

Releases the camera – After invocation other applications can access the camera hardware.

5.4 keycapture — Interface for global capturing of key events.

The `keycapture` module offers an API for global capturing of key events. The `keycapture` module provides the `KeyCapturer` object as a tool for listening the events.

The `KeyCapturer` object uses a callback method to report the key events. The callback method is called each time any of the specified keys is pressed.

Currently the `keycapture` module does not support capturing separate key-up or key-down events.

Note: Keycapture module requires capability `SwEvent` to work in 3rd Edition devices.

5.4.1 Module Level Constants

The following constants are defined in the `keycapture` module:

`all_keys`

A list of all key codes defined in the `key_codes` module.

5.4.2 KeyCapturer objects

`KeyCapturer` object takes a callback method as a mandatory parameter to its constructor. The callback method must have one single parameter for forwarding the key code of the captured key.

There can be several `KeyCapturer` objects existing at the same time.

`KeyCapturer` object has following methods and properties:

`keys`

List of keys to be captured. Can be read and written.

Example:

```
keys = (key_codes.EkeyUpArrow,)
keys = keycapture.all_keys
```

forwarding

Specifies whether captured key events are forwarded to other applications or not. Either has value 1 or 0. Can be read and written.

start()

Starts the actual capturing of key events.

stop()

Stops the actual capturing of key events.

last_key()

Returns last key code that is captured.

5.5 topwindow — Interface for creating windows that are shown on top of other applications.

The `topwindow` module offers an API for creating windows that are shown on top of other applications and managing the content of these windows. Images can be inserted into the windows and the background color, visibility, corner type and shadow of the window can be manipulated.

`topwindow` extension does not provide sophisticated drawing capabilities by any means but rather relies on services provided by the `graphics` extension: `topwindow` allows `graphics` `Image` objects to be put into the windows that are represented by `TopWindow` objects.

`TopWindow` object provides mainly only two services: `TopWindow` objects can be shown or hidden and Images can be put into the windows. However, several images can be added into one `TopWindow` object and several `TopWindow` objects can be created and shown. Since the images can be manipulated using the `graphics` extension this makes it possible to create many kind of content to the `TopWindow` objects.

5.5.1 TopWindow objects

class TopWindow()

Create a `TopWindow` object.

`TopWindow` objects have the following methods and properties:

show()

Shows the window. The window is not shown until `show()` is called.

hide()

Hides the window.

add_image(image, position)

Inserts an image object `graphics.Image` into the window. The position of the image is specified by the `(position)` parameter. If only the coordinates of the top left corner are specified, like `(x1, y1)` the image is not resized. If four coordinates are given, like `(x1, y1, x2, y2)`, the image is resized to fit to the specified area. Example:

```
add_image(image, (10,20))
add_image(image, (10,20,20,30))
```

remove_image(image[, position])

Removes the image from the window. Mandatory parameter `image` must be a `graphics.Image` object. Parameter `position` may specify the top-left corner coordinates of the image or the rectangular area of the image. If only `image` parameter is given, all the pictures representing this image object are removed from the window. If both parameters are given, only the picture that matches both parameters is removed.

Example:

```
remove_image(image)
remove_image(image, (10,10))
remove_image(image, (10,10,20,20))
```

position

Specifies the coordinates of the top left corner of the window. Can be read and written.

Example:

```
position = (10, 20)
```

size

Specifies the size of the window. Can be read and written.

Example:

```
size = (100, 200)
```

images

The images inserted into the window. Defined as a list of tuple objects. Each tuple contains a `graphics.Image` object and the *position* of the image. The *position* may specify the top-left coordinate of the image and optionally also the bottom-right coordinate of the image. Parameter (x,y) specifies the top-left coordinate, but does not resize the image while parameter like (x1,y1,x2,y2) specifies both the top-left and bottom-right coordinates and possibly also resizes the image. Can be read and written. Also see the `add_image()` and `remove_image()` methods.

Example:

```
images = [(image1,(x1,y1)), (image2,(x1,y1,x2,y2)), (image3,(50,50,100,100))]
```

sets the window content to be 3 images. `image2` and `image3` are possibly resized while the `image1` is not)

shadow

Specifies if the shadow of the window is shown and the length of the shadow. Can be read and written. Setting `shadow = 0` makes the shadow invisible.

Example: `shadow = 5`

corner_type

Specifies the corner type of the window. Can be read and written. Corner type can be one of the following values:

- square
- corner1
- corner2
- corner3
- corner5

Example: `corner_type = square`

maximum_size

Returns the maximum size of the window as a tuple (width, height). Read only property.

background_color

The background color of the window as an integer (e.g. `0xaabbcc`). The two greatest hexadecimal digits specify the red, the next two specify the blue and the last ones specify the green color. Can be read and written.

Example: `background_color = 0xffffffff` (sets the white color)

visible

Can be set to 0 or 1. 1 means that window is visible, 0 means that it is not. Can be read and written. Also see the `show` and `hide` methods.

5.6 gles — Bindings to OpenGL ES

The `gles` module provides Python bindings to OpenGL ES 2D/3D graphics C API. OpenGL ES is a standard defined by Khronos Group (www.khronos.org). Currently S60 Python supports OpenGL ES version 1.0 from Series 60 version 2.6 onwards. Support for OpenGL ES version 1.1 should also become available in the near future, and both versions are documented here. OpenGL ES 1.1 will require Series 60 version 3.0 or newer.

For detailed description of the OpenGL ES API see the official specifications at <http://www.khronos.org/opengles>. This documentation contains only information that is specific to the S60 Python bindings to OpenGL ES. Where possible, the conventions of the PyOpenGL desktop OpenGL bindings (<http://pyopengl.sourceforge.net>) have been followed.

The display of OpenGL ES graphics is handled by separate module, `glcanvas`. See `glcanvas` module documentation for more information.

5.6.1 array type

`gles` module defines `array` type for representing numerical data of specific GL type. `array` objects are convenient when numerical data for OpenGL ES calls is specified in Python code. Class `array` also defines the standard Python sequence methods so its instances can be iterated and individual items in arrays can be manipulated easily.

class `array`(*type*, *dimension*, *sequence*)

Constructs a new `array` object that contains the given type of data that is taken from *sequence*. Parameter *dimension* specifies how many items there are in each array element. The dimension information is stored with the array and is used by those functions that need to know the element size of the input data, for example, if colors are specified with three or four components. The dimension does not affect the length of an array or its indexing: both are based on individual items.

Value of *type* must be one of the following: `GL_FLOAT`, `GL_BYTE`, `GL_UNSIGNED_BYTE`, `GL_SHORT`, `GL_UNSIGNED_SHORT`, or `GL_FIXED`.

The data in *sequence* is flattened before it is used to fill the array. When *type* is `GL_FLOAT`, the sequence can contains floats or integers. With all other types, *sequence* must only contain integers. Values in *sequence* are casted in C to the requested type, so if the requested type cannot properly represent all the values the results can be unexpected.

`__len__`()

Returns the number of items in the array. Note that array dimension does not affect the calculation of the length.

`__getitem__`(*index*)

Returns the item in array with *index*. Note that array dimension does not affect indexing.

`__setitem__`(*index*, *value*)

Sets the value of the item in position *index* to *value*. Note that array dimension does not affect indexing.

5.6.2 Error handling

Errors generated by the API calls are handled similarly as in PyOpenGL: all GL errors are reported as Python exceptions of type `gles.GLError`. The wrapper code checks GL error status after each call automatically. There is no Python binding for `glGetError` call.

5.6.3 Differences to OpenGL ES C API

Certain OpenGL ES functions require special handling in Python, mainly because of the pointer parameters in the C API. Additionally, special Python versions for some OpenGL ES functions have been

added. Both of sets of functions are documented below. If a function is not listed here its Python version should exactly match the C version defined in the official OpenGL ES 1.0 and 1.1 specifications.

OpenGL ES 1.0

`glColorPointer(size, type, stride, sequence)`

Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the type and dimension of its data are ignored and *size* and *type* are used instead.

`glColorPointerub(sequence)`

Special Python version of `glColorPointer` that accepts either a `gles.array` object or some other Python sequence object. Other parameters of `glColorPointer` will be determined as follows:

- *size* If *sequence* is an instance of `gles.array`, its dimension is used; otherwise the length of *sequence* is used.
- *type* `GL_UNSIGNED_BYTE`
- *stride* 0

`glColorPointerf(sequence)`

Special Python version of `glColorPointer` that behaves exactly as `glColorPointerub` except `GL_FLOAT` is used as *type*.

`glColorPointerx(sequence)`

Special Python version of `glColorPointer` that behaves exactly as `glColorPointerub` except `GL_FIXED` is used as *type*.

`glCompressedTexImage2D(target, level, internalformat, width, height, border, imageSize, data)`

Parameter *data* must be either a `gles.array` or a Python string.

`glCompressedTexSubImage2D(target, level, xoffset, yoffset, width, height, format, imageSize, data)`

Parameter *data* must be either a `gles.array` or a Python string.

`glDeleteTextures(sequence)`

Parameter *sequence* must be a Python sequence containing integers.

`glDrawElements(mode, count, type, indices)`

Parameter *indices* must be either a `gles.array` or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the type of its data is ignored and *type* is used instead.

`glDrawElementsub(mode, indices)`

Special Python version of `glDrawElements` that uses length of the sequence *indices* as *count* and `GL_UNSIGNED_BYTE` as *type*.

`glDrawElementsus(mode, indices)`

Special Python version of `glDrawElements` that uses length of the sequence *indices* as *count* and `GL_UNSIGNED_SHORT` as *type*.

`glFogv(pname, params)`

Parameter *params* must be a Python sequence containing float values.

`glFogxv(pname, params)`

Parameter *params* must be a Python sequence containing integer values.

`glGenTextures(n)`

The generated texture names are returned in a Python tuple.

`glGetIntegerv(pname)`

The values are returned in a Python tuple.

`glGetString(name)`

The value is return as a Python string.

`glLightModelfv(pname, params)`

Parameter *params* must be a Python sequence containing float values.

`glLightModelxv(pname, params)`
Parameter *params* must be a Python sequence containing integer values.

`glLightfv(light, pname, params)`
Parameter *params* must be a Python sequence containing float values.

`glLightxv(light, pname, params)`
Parameter *params* must be a Python sequence containing integer values.

`glLoadMatrixf(m)`
Parameter *m* must be a Python sequence containing float values. The sequence is flattened before its items are read.

`glLoadMatrixx(m)`
Parameter *m* must be a Python sequence containing integer values. The sequence is flattened before its items are read.

`glMaterialfv(face, pname, params)`
Parameter *params* must be a Python sequence containing float values.

`glMaterialxv(face, pname, params)`
Parameter *params* must be a Python sequence containing integer values.

`glMultMatrixf(m)`
Parameter *m* must be a Python sequence containing float values. The sequence is flattened before its items are read.

`glMultMatrixx(m)`
Parameter *m* must be a Python sequence containing integer values. The sequence is flattened before its items are read.

`glNormalPointer(type, stride, sequence)`
Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the type of its data is ignored and *type* is used instead.

`glNormalPointerb(sequence)`
Special Python version of `glNormalPointer` that uses *type* `GL_BYTE` and *stride* `0`.

`glNormalPointers(sequence)`
Special Python version of `glNormalPointer` that uses *type* `GL_SHORT` and *stride* `0`.

`glNormalPointerf(sequence)`
Special Python version of `glNormalPointer` that uses *type* `GL_FLOAT` and *stride* `0`.

`glNormalPointerx(sequence)`
Special Python version of `glNormalPointer` that uses *type* `GL_FIXED` and *stride* `0`.

`glReadPixels(x, y, width, height, format, type)`
The pixel data read is returned in a Python string.

`glTexCoordPointer(size, type, stride, sequence)`
Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the dimension and type of its data are ignored and *size* and *type* are used instead.

`glTexCoordPointerb(sequence)`
Special Python version of `glTexCoordPointer` that accepts either a `gles.array` object or some other Python sequence object. Other parameters of `glTexCoordPointer` will be determined as follows:

- *size* If *sequence* is an instance of `gles.array`, its dimension is used; otherwise the length of *sequence* is used.
- *type* `GL_BYTE`
- *stride* `0`

`glTexCoordPointers(sequence)`

Special Python version of `glTexCoordPointer` that behaves exactly as `glTexCoordPointerb` except `GL_SHORT` is used as *type*.

`glTexCoordPointerf(sequence)`

Special Python version of `glTexCoordPointer` that behaves exactly as `glTexCoordPointerb` except `GL_FLOAT` is used as *type*.

`glTexCoordPointerx(sequence)`

Special Python version of `glTexCoordPointer` that behaves exactly as `glTexCoordPointerb` except `GL_FIXED` is used as *type*.

`glTexEnvfv(face, pname, params)`

Parameter *params* must be a Python sequence containing float values.

`glTexEnvxv(face, pname, params)`

Parameter *params* must be a Python sequence containing integer values.

`glTexImage2D(target, level, internalformat, width, height, border, format, type, pixels)`

Parameter *pixels* must be either a Python string, a `gles.array` object, or `graphics.Image` object. Python strings are taken as literal data with no conversion. The dimension and type of data in `gles.array` objects are ignored: the raw data in the array is used.

Use of `graphics.Image` objects is limited to only some combinations of *format* and *type*. Table 5.6.3 below shows the accepted combinations. To get the best results and performance, the `CFbsBitmap` object in the `graphics.Image` object should be in the equivalent display mode, also shown in the table below. Otherwise, the `CFbsBitmap` object will be first converted to the equivalent display mode before reading its pixel data, which can degrade the visual quality in some cases.

Table 5.1: Legal combinations of *format* and *type* with the equivalent Symbian display mode.

<i>format</i>	<i>type</i>	The equivalent display mode
<code>GL_LUMINANCE, GL_ALPHA</code>	<code>GL_UNSIGNED_BYTE</code>	EGray256
<code>GL_RGB</code>	<code>GL_UNSIGNED_BYTE</code>	EColor16M
<code>GL_RGB</code>	<code>GL_UNSIGNED_SHORT_5_6_5</code>	EColor64K

`glTexSubImage2D(target, level, xoffset, yoffset, width, height, format, type, pixels)`

The handling of *pixels* is the same as with `glTexImage2D`.

`glVertexPointer(size, type, stride, sequence)`

Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the dimension and type of its data are ignored and *size* and *type* are used instead.

`glVertexPointerb(sequence)`

Special Python version of `glVertexPointer` that accepts either a `gles.array` object or some other Python sequence object. Other parameters of `glVertexPointer` will be determined as follows:

- *size* If *sequence* is an instance of `gles.array`, its dimension is used; otherwise the length of *sequence* is used.
- *type* `GL_BYTE`
- *stride* 0

`glVertexPointers(sequence)`

Special Python version of `glVertexPointer` that behaves exactly as `glVertexPointerb` except `GL_SHORT` is used as *type*.

`glVertexPointerf(sequence)`

Special Python version of `glVertexPointer` that behaves exactly as `glVertexPointerb` except `GL_FLOAT` is used as *type*.

`glVertexPointerx(sequence)`

Special Python version of `glVertexPointer` that behaves exactly as `glVertexPointerb` except

GL_FIXED is used as *type*.

OpenGL ES 1.1

`glBufferData(target, size, data, usage)`

Parameter *data* must be a `gles.array` object. If *size* is -1, the in-memory size of *data* is used in its place.

`glBufferDatab(target, data, usage)`

Special Python version of `glBufferData` that accepts either a `gles.array` object or some other Python sequence object for *data*. If `gles.array` object is used, its in-memory size in bytes is used as *size*. Other sequences are first converted to flat lists of GL_BYTE data by casting. The length of the resulting sequence in bytes is used as *size*.

`glBufferDataub(target, data, usage)`

Special Python version of `glBufferData` that works exactly like `glBufferDatab` except GL_UNSIGNED_BYTE is used instead of GL_BYTE.

`glBufferDatas(target, data, usage)`

Special Python version of `glBufferData` that works exactly like `glBufferDatab` except GL_SHORT is used instead of GL_BYTE.

`glBufferDataus(target, data, usage)`

Special Python version of `glBufferData` that works exactly like `glBufferDatab` except GL_UNSIGNED_SHORT is used instead of GL_BYTE.

`glBufferDataf(target, data, usage)`

Special Python version of `glBufferData` that works exactly like `glBufferDatab` except GL_FLOAT is used instead of GL_BYTE.

`glBufferDataax(target, data, usage)`

Special Python version of `glBufferData` that works exactly like `glBufferDatab` except GL_FIXED is used instead of GL_BYTE.

`glBufferSubData(target, size, data, usage)`

Parameter *data* must be a `gles.array` object. If *size* is -1, the in-memory size of *data* is used in its place.

`glBufferSubDatab(target, data, usage)`

Special Python version of `glBufferSubData` that accepts either a `gles.array` object or some other Python sequence object for *data*. If `gles.array` object is used, its in-memory size (in bytes) is used as *size*. Other sequences are first converted to flat lists of GL_BYTE data by casting. The length of the resulting sequence is used as *size*.

`glBufferSubDataub(target, data, usage)`

Special Python version of `glBufferSubData` that works exactly like `glBufferSubDatab` except GL_UNSIGNED_BYTE is used instead of GL_BYTE.

`glBufferSubDatas(target, data, usage)`

Special Python version of `glBufferSubData` that works exactly like `glBufferSubDatab` except GL_SHORT is used instead of GL_BYTE.

`glBufferSubDataus(target, data, usage)`

Special Python version of `glBufferSubData` that works exactly like `glBufferSubDatab` except GL_UNSIGNED_SHORT is used instead of GL_BYTE.

`glBufferSubDataf(target, data, usage)`

Special Python version of `glBufferSubData` that works exactly like `glBufferSubDatab` except GL_FLOAT is used instead of GL_BYTE.

`glBufferSubDataax(target, data, usage)`

Special Python version of `glBufferSubData` that works exactly like `glBufferSubDatab` except GL_FIXED is used instead of GL_BYTE.

`glClipPlanef(plane, equation)`

Parameter *equation* must be a Python sequence that contains four float values.

`glClipPlanex(plane, equation)`
 Parameter *equation* must be a Python sequence that contains four integer values.

`glDeleteBuffers(buffers)`
 Parameter *buffers* must be a Python sequence that contains integer values.

`glDrawTexsvOES(coords)`
 Parameter *coords* must be a Python sequence that contains integer values.

`glDrawTexivOES(coords)`
 Parameter *coords* must be a Python sequence that contains integer values.

`glDrawTexfvOES(coords)`
 Parameter *coords* must be a Python sequence that contains float values.

`glDrawTexfvOES(coords)`
 Parameter *coords* must be a Python sequence that contains integer values.

`glGenBuffers(n)`
 The generated buffer names are returned in a Python tuple.

`glGetBooleanv(pname)`
 The values are returned in a Python tuple.

`glGetBufferParameteriv(target, pname)`
 The value is returned as an integer.

`glGetClipPlanef(plane)`
 The values are returned in a Python tuple.

`glGetClipPlanef(plane)`
 The values are returned in a Python tuple.

`glGetFixedv(pname)`
 The values are returned in a Python tuple.

`glGetFloatv(pname)`
 The values are returned in a Python tuple.

`glGetLightfv(light, pname)`
 The values are returned in a Python tuple.

`glGetLightxv(light, pname)`
 The values are returned in a Python tuple.

`glGetMaterialfv(face, pname)`
 The values are returned in a Python tuple.

`glGetMaterialxv(face, pname)`
 The values are returned in a Python tuple.

`glGetTexEnvf(face, pname)`
 The values are returned in a Python tuple.

`glGetTexEnvx(face, pname)`
 The values are returned in a Python tuple.

`glGetTexParameterf(target, pname)`
 The value is returned as a float.

`glGetTexParameterx(target, pname)`
 The value is returned as an integer.

`glMatrixIndexPointerOES(size, type, stride, sequence)`
 Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the dimension and type of its data are ignored and *size* and *type* are used instead.

`glMatrixIndexPointerOESub(sequence)`

Special Python version of `glMatrixIndexPointerOES` that accepts either a `gles.array` object or some other Python sequence object. Other parameters of `glMatrixIndexPointerOES` will be determined as follows:

- *size* If *sequence* is an instance of `gles.array`, its dimension is used; otherwise the length of *sequence* is used.
- *type* `GL_UNSIGNED_BYTE`
- *stride* 0

`glPointParameterfv(pname, params)`

Parameter *params* must be a Python sequence containing float values.

`glPointParameterxv(pname, params)`

Parameter *params* must be a Python sequence containing integer values.

`glPointSizePointerOES(type, stride, sequence)`

Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the type of its data is ignored and *type* is used instead.

`glPointSizePointerOESf(sequence)`

Special Python version of `glPointSizePointerOES` uses `GL_FLOAT` as *type* and 0 as *stride*.

`glPointSizePointerOESx(target, data, usage)`

Special Python version of `glPointSizePointerOES` uses `GL_FIXED` as *type* and 0 as *stride*.

`glWeightPointerOES(size, type, stride, sequence)`

Parameter *sequence* must be either a `gles.array` object or some other Python sequence object. `gles.array` objects require less processing and can be therefore slightly faster. If `gles.array` object is used, the dimension and type of its data are ignored and *size* and *type* are used instead.

`glWeightPointerOESf(sequence)`

Special Python version of `glWeightPointerOES` that accepts either a `gles.array` object or some other Python sequence object. Other parameters of `glWeightPointerOES` will be determined as follows:

- *size* If *sequence* is an instance of `gles.array`, its dimension is used; otherwise the length of *sequence* is used.
- *type* `GL_FLOAT`
- *stride* 0

`glWeightPointerOESx(sequence)`

Special Python version of `glWeightPointerOES` that behaves exactly as `glWeightPointerOESf` except `GL_FIXED` is used as *type*.

5.7 glcanvas — UI Control for Displaying OpenGL ES Graphics

The `glcanvas` module provides a UI control, `GLCanvas`, for displaying OpenGL ES graphics. `GLCanvas` component is similar to the `appuifw Canvas` component that supports Symbian OS -level drawing.

Internally `GLCanvas` uses EGL for displaying the OpenGL ES graphics. EGL, as OpenGL ES, is a standard API defined by the Khronos Group (www.khronos.org). Specifically, `GLCanvas` uses an EGL window surface, which supports double-buffered rendering. It is possible to affect selection of the EGL config that is used to create the window surface; for details, see the documentation of the `GLCanvas` constructor.

`GLCanvas` instances also hold the OpenGL ES context object, which together with the surface, are needed for rendering. When one wants to render with a specific OpenGL ES context to a specific surface, they need to be *made current*. This also applies to `GLCanvas`, which has the `makeCurrent` method for this purpose. Generally, calling `makeCurrent` has to be done only if multiple `GLCanvas` objects are used in

the same program, as each `GLCanvas` object is automatically made current when it is created and it remains current until it is destroyed or `makeCurrent` of some other `GLCanvas` object is called.

class `GLCanvas`(*redraw_callback*, [*event_callback=*`None`, *resize_callback=*`None`, *attributes=*`None`])

Constructs a new `GLCanvas` object that can be used as a UI control for displaying OpenGL ES graphics. Parameters *redraw_callback*, *event_callback*, and *resize_callback* have the same meaning as with `appuifw` module `Canvas`. Using *redraw_callback* to specify the OpenGL ES drawing is preferred as it will be automatically called by `drawNow` method.

Parameter *attributes* can be used to specify attributes used in EGL config selection. It must be a Python dictionary where keys are EGL attribute names (which are defined in the `glcanvas` module) and values are integers defining the desired attribute values. Unless specified in *attributes*, `EGL_BUFFER_SIZE` is set to value based on the display mode of the window owned by the underlying `CCoeControl` object and `EGL_DEPTH_SIZE` is set to 16. Attributes specified in *attributes* are given to `eglChooseConfig`. Refer to the EGL specification for a detailed list of config attributes and explanation of how the selection of EGL configs works.

The new `GLCanvas` object will be made current when the constructor returns so `makeCurrent` does not have to be called before starting to use OpenGL ES calls.

`bind`(*key_code*, *c*)

Sets a callback to be called when a specific key is pressed. Parameter *key_code* should be one of the standard Symbian key codes defined in `key_codes`. Parameter *c* must be a callable object.

`drawNow`()

Calls the redraw callback (if set) and then calls `eglSwapBuffers` to render and display the OpenGL ES graphics.

`makeCurrent`()

Makes this `GLCanvas` object current, meaning that it will be used to display the results of the subsequent OpenGL ES calls. In EGL terms this means that the EGL context and surface held by this object will be passed to `eglMakeCurrent`. Using `makeCurrent` makes it possible to use several `GLCanvas` objects in a single application: the receiver of the OpenGL ES calls can be switched with `makeCurrent` easily.

Audio and Communication Services

6.1 audio — An audio related services package

The `audio` module enables recording and playing audio files and access to device text-to-speech engine. The `audio` module supports all the formats supported by the device, typically: WAV, AMR, MIDI, MP3, AAC, and Real Audio¹. For more information on the audio types supported by different devices, see the *Forum Nokia* Web site [7] and *S60 Platform* Web site [8].

The following `Sound` class static methods are defined in the `audio` module:

`Sound.open(filename)`

Returns a new initialized `Sound` object with the named file opened. Note that *filename* should be a full Unicode path name and must also include the file extension, for example `u'c:\\foo.wav'`.

The following data items for state information are available in `audio`:

`ENotReady`

The `Sound` object has been constructed but no audio file is open.

`EOpen`

An audio file is open but no playing or recording operation is in progress.

`EPlaying`

An audio file is playing.

`ERecording`

An audio file is being recorded.

The following data item is provided for continuous playback of an audio file:

`KMdaRepeatForever`

Possible value for *times* parameter in `open`.

The following method is available in the `audio` module:

`say(text, prefix=audio.TTS_PREFIX)`

Passes the `text` to the device text-to-speech engine. The default `prefix` is the text-to-speech prefix `"(tts)"`.

6.1.1 Sound Objects

Note: The method `current_volume` is not available for S60 1st Edition.

class `Sound`

`Sound` objects have the following functions:

`play([times=1, interval=0, callback=None])`

Starts playback of an audio file from the beginning. Without the parameters *times* and

¹The dynamically loaded audio codec for the sound file is based on the MIME-type information inside the audio file and file extension.

interval it plays the audio file one time. *times* defines the number of times the audio file is played, the default being 1. If the audio file is played several times, *interval* gives the time interval between the subsequent plays in microseconds.

The optional callback is called when the playing starts and when the end of the sound file is reached. The callback should take three parameters: the previous state, the current state and the possible error code. The possible states given as parameters to the callback are data items in the module `audio`.

Other issues:

- Calling `play(audio.KMdaRepeatForever)` will repeat the file forever.
- If an audio file is played but not stopped before exiting, the Python script will leave audio playing on; therefore `stop` needs to be called explicitly prior to exit.
- Currently the module does not support playing simultaneous audio files, calling `play` to a second `Sound` instance while another audio file is playing, stops the earlier audio file and starts to play the second `Sound` instance.
- Calling `play` while a telephone call is ongoing plays the sound file to uplink. In some devices the sound file is also played to the device speaker.
- Calling `play` when already playing or recording results in `RuntimeError`. Calling `stop` prior to `play` will prevent this from happening.

`stop()`

Stops playback or recording of an audio file.

`record()`

Starts recording audio data to a file. If the file already exists, the operation appends to the file. For Nokia devices, WAV is typically supported for recording. For more information on the audio types supported by different devices, see the *Forum Nokia* Web site [7] and *S60 Platform* Web site [8]. Other issues:

- Calling `record` while a telephone call is ongoing starts the recording of the telephone call.
- Calling `record` when already playing or recording results in `RuntimeError`. Calling `stop` prior to `record` will prevent this from happening.

`close()`

Closes an opened audio file.

`state()`

Returns the current state of the `Sound` type instance. The different states (constants) are defined in the `audio` module. The possible states² are:

- `ENotReady`
The `Sound` object has been constructed but no audio file is open.
- `EOpen`
An audio file is open but no playing or recording operation is in progress.
- `EPlaying`
An audio file is playing.
- `ERecording`
An audio file is being recorded.

`max_volume()`

Returns the maximum volume of the device.

`set_volume(volume)`

Sets the volume. If the given volume is negative, then the volume is set to zero which mutes the device. If the volume is greater than `max_volume`, then `max_volume` is used.

`current_volume()`

Returns the current volume set.

`duration()`

Returns the duration of the file in microseconds.

`set_position(microseconds)`

Set the position for the playhead.

²Descriptions for these options are based on information found in S60 SDK documentation [4].

`current_position()`

Returns the current playhead position in microseconds.

6.2 telephone — Telephone services

This module provides an API to a telephone.

Since the users of the device can also hang-up the phone explicitly, they might affect the current status of the call. In addition, using this extension in an emulator has no effect since no calls can be connected.

The `telephone` module has the following functions:

`dial(number)`

Dials the number set in *number*. *number* is a string, for example `u'+358501234567'` where `'+'` is the international prefix, `'358'` is the country code, `'50'` is the mobile network code (or the area code), and `'1234567'` is the subscriber number. If there is an ongoing phone call prior to calling `dial` from Python, then the earlier call is put on hold and a new call is established. Calling `dial` multiple times when, for example, the first call has been answered and a line has been established results in subsequent calls not being connected.

`hang_up()`

Hangs up if a call initiated by `dial` is in process. If this call has already been finished, `SymbianError: KErrNotReady` is raised.

6.3 messaging — A messaging services package

The `messaging` module offers APIs to messaging services. Currently, the `messaging` module has functions:

`sms_send(recipient, message, [encoding='7bit', callback=None])`

Sends an SMS message with body text *message* (Unicode) to telephone number *recipient* (string).

The optional parameter *encoding* is used to define encoding in the message. The parameter values can be `'7bit'`, `'8bit'` or `'UCS2'`.

The optional parameter *callback* is invoked with the current status of the send operation as parameter. The possible states are data items in the module `messaging`. Invoking another send while a previous send request is ongoing will result in `RuntimeError` being raised.

If the callback is not given, the `sms_send` function will block until the message in the queue is either deleted or the sending has failed³.

`mms_send(recipient, message, [attachment=None])`

Note: Available from S60 3.0 onwards (inclusive).

Sends an MMS message with body text *message* (Unicode) to telephone number *recipient* (string).

The optional parameter *attachment* is full path to e.g. image file attached to the message.

The following data items for SMS sending state information are available in the module `messaging`:

`ECreated`

`EMovedToOutBox`

`EScheduledForSend`

`ESent`

The SMS message has been sent.

`EDeleted`

The SMS message has been deleted from device's outbox queue. The `sms_send` operation has finalized and subsequent SMS sending is possible.

³Please note that this blocking might last for several minutes and hence supplying the callback might be more suitable in many cases.

EScheduleFailed

ESendFailed

This state information is returned when the SMS subsystem has tried to send the message several times in vain. The `sms_send` operation has finalized and subsequent SMS sending is possible.

ENoServiceCentre

This state information is returned by the SMS subsystem in S60 3.x emulator. In emulator this indicates that the `sms_send` operation has finalized and subsequent SMS sending is possible.

EFatalServerError

The underlying messaging subsystem in S60 devices might give error messages to the user if the device is not connected to a network while trying to send a message – An "SMS send failed!" note is a common error message.

When sending messages in offline-mode or with no network connection these messages are actually added to an outgoing message queue and they might be sent if the device is later on connected to a suitable network⁴. This occurs despite the possibly misleading error messages. The current network conditions can be checked e.g. with `sysinfo.active_profile()` and `sysinfo.signal_bars()` invocations.

The following is example code for state information processing with `sms_send` operation:

```
>>> import messaging
>>>
>>> def cb(state):
...     if state==messaging.ESent:
...         print "**Message was sent**"
...     if state==messaging.ESendFailed:
...         print "**Something went wrong - Truly sorry for this**"
...
>>> messaging.sms_send("1234567", "Hello from PyS60!", '7bit', cb)
>>> **Message was sent** # This is printed from the callback
```

6.4 inbox — Interface to device inbox

The `inbox` module offers APIs to device inbox. Currently, the `inbox` module supports only SMS handling and notifications of incoming messages and drafts, sent and outbox folders are not supported.

class `Inbox()`

Create an `Inbox` object.

6.4.1 Inbox Objects

`Inbox` objects have the following functions:

messages()

Returns a list of SMS message IDs in device inbox.

content(*sms_id*)

Retrieve the SMS message content in Unicode.

time(*sms_id*)

Retrieve the SMS message time of arrival in seconds since epoch.

address(*sms_id*)

Retrieve the SMS message sender address in Unicode.

⁴Note also that prior this the user of the device can explicitly delete the messages from the native messaging application. The amount of resending is approx. 4 times – After this the sending operation is cancelled and the user of the device will see a visual cue of the failure in the status pane.

`delete(sms_id)`

Delete the SMS message from inbox.

`unread()`

`sms_id`) Returns the status (1=unread, 0=read) of the SMS with `id`.

`bind(callable)`

Bind a callback to receive new message events in device inbox. When a new message arrives to the device inbox the `callback` gets called with the received message ID. The received message can be other than an SMS message.

If the message received is deleted immediately after e.g. checking the message content, the "new message" sound and dialog are not activated. This functionality might be useful in notification type of applications.

Examples:

```
>>> import inbox
>>> i=inbox.Inbox()
>>> m=i.sms_messages()
>>> i.content(m[0])
u'foobar'
>>> i.time(m[0])
1130267365.03125
>>> i.address(m[0])
u'John Doe'
>>> i.delete(m[0])
>>>

>>> import inbox
>>> id=0
>>> def cb(id_cb):
...     global id
...     id=id_cb
...
>>> i=inbox.Inbox()
>>> i.bind(cb)
>>> # Send an SMS to your inbox here. The "id" gets updated
>>> i.address(id)
u'John Doe'
>>> i.content(id)
u'print 1'
>>>
```

6.5 location — GSM location information

The `location` module offers APIs to location information related services. Currently, the `location` has one function:

Note: Location module requires capabilities `ReadDeviceData`, `ReadUserData` and `Location` in 3rd Edition devices.

`gsm_location()`

Retrieves GSM location information: Mobile Country Code, Mobile Network Code, Location Area Code, and Cell ID. A location area normally consists of several base stations. It is the area where the terminal can move without notifying the network about its exact position. `mcc` and `mnc` together form a unique identification number of the network into which the phone is logged.

6.5.1 Examples

Here is an example of how to use the `location` package to fetch the location information:

```
>>> import location
>>> print location.gsm_location()
```

6.6 position — Simplified interface to the Location Acquisition API

The `position` provides basic access to the S60 Location Acquisition API. The Location Acquisition API gathers different positioning technologies together to be used through a consistent interface. Location Acquisition API offers quite a large amount of information (cost of service, device power consumption etc.) about accessible positioning devices (like GPS-modules), position, course, accuracy and satellite information (depending on the position device used) and much more. The Location Acquisition API can also be used to obtain device/vendor specific extended information.

The `position` module has the following functions:

```
modules()
    get information about available positioning modules

default_module()
    get default module id

module_info(module_id)
    get detailed information about the specified module

select_module(module_id)
    select a module

set_requestors(requestors)
    set the requestors of the service (at least one must be set)

position(course=0,satellites=0)
    get the position information
```

6.6.1 Example

The following example demonstrates how to use the python `position` module.

```
# information about available positioning modules
print "***available modules***"
print positioning.modules()
print ""

# id of the default positioning module
print "***default module***"
print positioning.default_module()
print ""

# detailed information about the default positioning module
print "***detailed module info***"
print positioning.module_info(positioning.default_module())
print ""

# select a module (however, selecting default module has no
# relevance..this has been added just to show the functionality).
positioning.select_module(positioning.default_module())

# set requestors.
# at least one requestor must be set before requesting the position.
# the last requestor must always be service requestor
# (whether or not there are other requestors).
positioning.set_requestors([{"type": "service",
```

```

        "format":"application",
        "data":"test_app"}})

# get the position.
# note that the first position()-call may take a long time
# (because of gps technology).
print "***position info***"
print positioning.position()
print ""

# re-get the position.
# this call should be much quicker.
# ask also course and satellite information.
print "***course and satellites***"
print positioning.position(course=1,satellites=1)
print ""

```

To run the script in the emulator you must configure PSY emulation (SimPSYConfigurator->Select Config File -><some config file s>).

Data Management

7.1 contacts — A contacts related services package

The `contacts` module offers an API to address book services allowing the creation of contact information databases. The `contacts` module represents a Symbian contact database as a dictionary-like `ContactDb` object, which contains `Contact` objects and which is indexed using the unique IDs of those objects. A `Contact` object is itself a list-like object, which contains `ContactField` objects and which is indexed using the field indices. Unique IDs and field indices are integers. The `ContactDb` object supports a limited subset of dictionary functionality. Therefore, only `__iter__`, `__getitem__`, `__delitem__`, `__len__`, `keys`, `values`, and `items` are included.

`ContactDb` objects represent a live view into the database. If a contact is changed outside your Python application, the changes are visible immediately, and conversely any changes you commit into the database are visible immediately to other applications. It is possible to lock a contact for editing, which will prevent other applications from modifying the contact for as long as the lock is held. This can be done in, for example, a contacts editor application when a contact is opened for editing, very much like with the Contacts application in your Nokia device. If you try to modify a contact without locking it for editing, the contact is automatically locked before the modification and released immediately afterwards.

7.1.1 Module Level Functions

The following free functions - functions that do not belong to any class - are defined in the `Contact` module:

```
open([filename[, mode]])
```

Opens a contacts database and returns a `ContactDb` object. *filename* should be a full Unicode path name. If *filename* is not given, opens the default contacts database. If *mode* is not given, the database must exist. If *mode* is 'c', the database is created if it does not already exist. If *mode* is 'n', a new, empty database is created, overwriting the possible previous database.

Warning: Using `open` together with the additional parameters *filename* or *mode* is intended for testing purposes only. Due to S60 SDK functionality, the `open` method can sometimes be unreliable with these parameters.

7.1.2 ContactDb Object

There is one default contact database, but it is possible to create several databases with the `open` function.

```
class ContactDb
```

`ContactDb` objects have the following methods:

```
add_contact()
```

Adds a new contact into the database. Returns a `Contact` object that represents the new contact. The returned object is already locked for modification. Note that a newly created contact will contain some empty default fields. If you do not want to use the default fields for anything, you can ignore them.

`find(searchterm)`
 Finds the contacts that contain the given Unicode string as a substring and returns them as a list.

`import_vcards(vcards)`
 Imports the vCard(s) in the given string into the database.

`export_vcards(ids)`
 Converts the contacts corresponding to the ID's in the given tuple *ids* to vCards and returns them as a string.

`keys()`
 Returns a list of unique IDs of all `Contact` objects in the database.

`compact_required()`
 Verifies whether compacting is recommended. Returns an integer value indicating either a true or false state. Returns `True` if more than 32K of space is unused and if this comprises more than 50 percent of the database file, or if more than 256K is wasted in the database file.

`compact()`
 Compacts the database to its minimum size.

`__delitem__(id)`
 Deletes the given contact from the database.

`field_types()`
 Returns a list of dictionary objects that contains information on all supported field types. The list contains dictionary objects, which each describe one field type. The most important keys in the dictionary are `'type'` and `'location'` which together indentify the field type. `'type'` can have string values such as `'email_address'`. `'location'` can have the string values `'none'`, `'home'`, or `'work'`. Another important key is `'storagetype'`, which defines the storage type of the field. `'storagetype'` can have the string values `'text'`, `'datetime'`, `'item_id'`, or `'binary'`. Note that the `Contacts` extension does not support adding, reading, or modifying fields of any other type than `'text'` or `'datetime'`. The other content returned by `field_types` is considered to be advanced knowledge and is not documented here.

`groups`
 Returns contact groups of the database. Read-only.

7.1.3 Contact Object

A `Contact` object represents a live view into the state of a single contact in the database. You can access the fields either with a contact's numeric field ID as `contact[fieldid]`, or using the `find` method. Attempting to modify a contact while it has been locked for editing in another application will raise the exception `ContactBusy`.

`class Contact`

`Contact` objects have the following attributes:

`id`
 The unique ID of this `Contact`. Read-only.

`title`
 The title of this `Contact`. Read-only.

`is_group`
 Returns 1 if this contact is a contact group. Returns 0 if normal contact entry. Read-only.

`Contact` objects have the following methods:

`begin()`
 Locks the contact for editing. This prevents other applications from modifying the contact for as long as the lock is held. This method will raise the exception `ContactBusy` if the contact has already been locked.

`commit()`
 Releases the lock and commits the changes made into the database.

`rollback()`

Releases the lock and discards all changes that were made. The contact remains in the state it was before `begin`.

`as_vcard()`

Returns the contact as a string in vCard format.

`add_field(type [, value [, label=field_label][, location=location_spec]])`

Adds a new field into this `Contact`. This method raises `ContactBusy` if the contact has been locked by some other application. *type* can be one of the supported field types as a string.

In Series 60 editions older than the 3rd one the following field types can be added:

- city
- company_name
- country
- date
- dtmf_string
- email_address
- extended_address
- fax_number
- first_name
- job_title
- last_name
- mobile_number
- note
- pager_number
- phone_number
- po_box
- postal_address
- postal_code
- state
- street_address
- url
- video_number
- wvid

The following field types are recognized but cannot be created:

- first_name_reading
- last_name_reading
- picture
- speed_dial
- thumbnail_image
- voicetag

If 3rd edition of Series 60 is used the following field types can be added:

- city
- company_name
- country
- date
- dtmf_string
- email_address
- extended_address
- fax_number
- first_name
- job_title

- last_name
- mobile_number
- note
- pager_number
- phone_number
- po_box
- postal_address
- postal_code
- state
- street_address
- url
- video_number
- picture
- second_name
- voip
- sip_id
- personal_ringtone
- share_view
- prefix
- suffix
- push_to_talk
- locationid_indication

The following field types are recognized but cannot be created at present:

- first_name_reading
- last_name_reading
- speed_dial
- thumbnail_image
- voice_tag
- wvid

All supported field types are passed as strings or Unicode strings, except for 'date' which is a float that represents Unix time. For more information on Unix time, see Section 3.5, Date and Time.

field_label is the name of the field shown to the user. If you do not pass a label, the default label for the field type is used.

location_spec, if given, must be 'home' or 'work'. Note that not all combinations of type and location are valid. The settings of the current contacts database in use determine which ones are valid.

`find([type=field_type][, location=field_location])`

Finds the fields of this contact that match the given search specifications. If no parameters are given, all fields are returned.

`__delitem__(fieldindex)`

Deletes the given field from this contact. Note that since this will change the indices of all fields that appear after this field in the contact, and since the `ContactField` objects refer to the fields by index, old `ContactField` objects that refer to fields after the deleted field will refer to different fields after this operation.

7.1.4 ContactField Object

A `ContactField` represents a field of a `Contact` at a certain index. A `ContactField` has attributes, some of which can be modified. If the parent `Contact` has not been locked for editing, modifications are committed immediately to the database. If the parent `Contact` has been locked, the changes are committed only when `commit` is called on the `Contact`.

class ContactField

ContactField objects have the following attributes:

label

The user-visible label of this field. Read-write.

value

The value of this field. Read-write.

type

The type of this field. Read-only.

location

The location of this field. This can be 'none', 'work', or 'home'.

schema

A dictionary that contains some properties of this field. The contents of this dictionary correspond to those returned by the ContactDb method `field_types`.

7.1.5 Groups Object

A **Groups** object represents Symbian contact groups as a dictionary like object with limited subset of dictionary functionality. Each group can be accessed using the group's unique id as a key. The Groups object returns a list like **Group** object as the value matching the given key.

The following common methods are supported: `__iter__`, `__getitem__`, `__delitem__` and `__len__`.

class Groups

Groups objects have the following attributes:

`add_group([name])`

Creates new contact group and returns corresponding **Group** object. Group name can be given as an optional parameter.

7.1.6 Group Object

A **Group** object represents single Symbian contact group as a list object with limited subset of list functionality. The **Group** object lists Contact entry ids that belong to the group.

The native Symbian group objects are represented as Symbian contact entries in the database. Therefore they can also be accessed as Python **Contact** objects, but this way their group handling properties cannot be used from Python. Use **Groups** and **Group** objects to access group functionalities.

The following common methods are supported: `__iter__`, `__getitem__`, `__delitem__` and `__len__`.

class Group

Group objects have the following attributes:

id

The unique id of the **Group** object. Read-only.

name

The name of the **Group** object. Read-write.




Figure 7.1: The calendar module objects

7.2 calendar — Access to calendar related services

The `calendar` module offers an API to calendar services. The `calendar` module represents a Symbian agenda database as a dictionary-like `CalendarDb` object, which contains `Entry` objects and which is indexed using the unique IDs of those objects. There are four types of entry objects: `AppointmentEntry`, `EventEntry`, `AnniversaryEntry`, and `TodoEntry`.

`CalendarDb` objects represent a live view into the database. If an entry is changed outside your Python application, the changes are visible immediately, and conversely any changes you commit into the database are visible immediately to other applications.

In addition to entries, there are todo lists which contain todo entries. Todo lists are accessed using the dictionary-like `TodoListDict` and `TodoList` objects.

All time parameters use Unix time unless stated otherwise. For more information on Unix time, see Section 3.5, Date and Time.

Figure 7.1 demonstrates the relationships of the `calendar` module objects.

7.2.1 Module Level Functions

The following free functions - functions that do not belong to any class - are defined in the `calendar` module:

`open([filename=None, mode=None])`

Opens a calendar database and returns a new `CalendarDb` object.

If `filename` is `None`, the default database is opened.

If `filename` is given, it should be a full, absolute path name in Unicode that specifies the calendar database to open.

`mode` can be:

- `None`: Opens an existing calendar database.
- `'c'`: Opens an existing calendar database, or creates it if it doesn't exist.
- `'n'`: Creates a new, empty calendar database. If `filename` exists, the previous contents are erased.

7.2.2 CalendarDb Objects

Calendar entries and todo lists are stored in a calendar database. There is one default calendar database but more calendar databases can be created by invoking `open` with parameters `'n'` or `'c'`.

class `CalendarDb`

`CalendarDb` objects have the following methods:

`add_appointment()`

Creates and returns a new appointment entry `AppointmentEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_event()`

Creates and returns a new event entry `EventEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_anniversary()`

Creates and returns a new anniversary entry `AnniversaryEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_todo()`

Creates and returns new todo entry `TodoEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`find_instances(start_date, end_date, search_str="u" [, appointments=0, events=0, anniversaries=0, todos=0])`

The parameters for this function include the start date, end date, search string, and optional parameters. The optional parameters define the entry types to be included into the search. By default all entry types are included. Returns a list that contains `Entry` instances found in the search. An instance is a dictionary that contains the entry ID and the datetime value. An entry may have several instances if it is repeated, for example once every week, etc. However, all the returned instances occur on the same day, i.e. on the first day between the start and end datetime values that contains instances. To search all instances between the initial start and end datetime values, you may have to execute several searches and change the start datetime value for each search. A match is detected if the search string is a substring of an entry's content.

`monthly_instances(month, appointments=0, events=0, anniversaries=0, todos=0)`

The parameters for this function include `month` (float) and optional parameters. The optional parameters define the entry types to be returned. Returns a list that contains entry instances occurring during the specified calendar month.

`daily_instances(day, appointments=0, events=0, anniversaries=0, todos=0)`

The parameters for this function include `day` (float) and optional parameters. The optional parameters define the entry types to be returned. Returns a list that contains entry instances occurring on the specified day.

`add_todo_list([name=None])`

Creates a new todo list. `name` sets the name of the todo list (Unicode). Returns the ID of the created todo list.

`export_vcalendars((int,...))`

Returns a `vcalendar` string that contains the specified entries in vCalendar format. The parameter for this function is a tuple that contains the entry IDs of the exported entries.

`import_vcalendars(string)`

Imports `vcalendar` entries, given in the string parameter, to the database. Returns a tuple that contains the unique IDs of the imported entries.

`todo_lists`

Contains a dictionary-like `TodoListDict` object for accessing the todo lists of this database.

`__delitem__(id)`

Deletes the given calendar `Entry` from the database. `id` is the unique ID of the calendar `Entry`.

`__getitem__(id)`

Returns a calendar `Entry` object indicated by the unique ID. The returned object can be one

of the following: `AppointmentEntry`, `EventEntry`, `AnniversaryEntry`, or `TodoEntry`. `id` is the unique ID of the calendar `Entry`.

`compact()`

Compacts the database file. The returned value (integer) indicates the success of compaction; a value other than zero means that the compaction was successful.

7.2.3 Entry Objects

An `Entry` object represents a live view into the state of a single entry in the database. You can access the entries with an entry's unique ID. If you create a new entry using `db.add_appointment` etc., it is saved into the database only if you call the entry's `commit` method. In case an entry is already saved into the database, the autocommit mode is on by default and all the changes are automatically saved into the database, unless you call the entry's `begin` method. If you call the entry's `begin` method, the changes are not saved into the database until you call the entry's `commit` method.

Database entries cannot be locked. In other words, other applications are able to make changes to the database entries you are using (not directly to the `EntryObjects` you are using, but to their representation in the database) at the same time you are modifying them, even if you use `begin` and `commit` methods.

class `Entry`

`Entry` objects have the following methods and properties:

`content`

Sets or returns the entry's content text (Unicode).

`commit()`

Saves the entry or in case of a new entry adds the entry into the database. Note that this can be called only in case of a new entry, created with `db.add_appointment` etc., or after `begin` is called.

`rollback()`

Undoes the changes made after last `commit`.

`set_repeat(dictionary)`

Sets the repeat data of the entry. *dictionary* is a repeat data dictionary that contains all the repeat rules. For more information on repeat rules, see Section 7.3.4, Repeat Rules.

`get_repeat()`

Returns the repeat data dictionary of the entry.

`location`

Sets or returns the entry's location data (Unicode), for example meeting room information.

`set_time(start[, end])`

Sets the start and end datetime values of the entry (floats). If only one parameter is given, the other will have the same value.

In case of events, anniversaries, and todo entries the datetime values are truncated to corresponding date values.

`TodoEntries` can be made undated with `TodoEntry.set_time(None)`. Making the todo entry undated means removing the start and end date and all the repeat rules.

`start_time`

The start datetime value (float) of the entry or `None` if the start datetime of the entry is not set.

`end_time`

The end datetime value (float) of the entry or `None` if the end datetime of the entry is not set.

`id`

The unique ID of the entry.

`last_modified`

The datetime value (float) of the entry's last modification in universal time.

alarm

The alarm datetime value (float) for the entry. `None` if `alarm` is not set. Alternatively removes the alarm if the value is set to `None`.

Alarms can be set to all `Entry` types. However, only alarms set to `Appointments` and `Anniversaries` will actually cause an alarm; this is similar to the Calendar application in your Nokia device, which allows you to set an alarm only for `Meetings` and `Anniversaries`. In addition, alarms set to any entries residing in a database other than the default database do not cause actual alarms either.

priority

The priority of the entry, which can be an integer ranging from 0 to 255. Native Phonebook and Calendar applications in Nokia devices use value 1 for high priority, 2 for normal priority, and 3 for low priority.

crossed_out

The crossed out value of an entry. A value that is interpreted as false means that the entry is not crossed out, whereas a value that is interpreted as true means that the entry is crossed out. Note that `TodoEntries` must also have a cross-out time while the other entry types cannot have one. If `TodoEntry` is crossed out using this method, the moment of crossing out is set to the cross-out time of the `TodoEntry`. See also Section 7.3.3, `TodoEntry`, `cross_out_time`.

replication

Sets or returns the entry's replication status, which can be one of the following: `'open'`, `'private'`, or `'restricted'`.

as_vcalendar()

Returns this entry as a vCalendar string.

AppointmentEntry Objects**class AppointmentEntry**

`AppointmentEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

EventEntry**class EventEntry**

`EventEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

AnniversaryEntry**class AnniversaryEntry**

`AnniversaryEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

TodoEntry

`TodoEntry` objects represent todo entry types. They have additional properties compared to the `Entry` class from which they are derived.

class TodoEntry

`TodoEntry` objects have the following additional properties:

cross_out_time

The cross-out date value of the entry. The value can be `None` meaning that the entry is not crossed out, or the cross-out date (float). The set value must be date (float). Setting a cross-out time also crosses out the entry. See also Section 7.3.3, `Entry Object`, `crossed_out`.

`todo_list`
The ID of the todo list to which this entry belongs.

TodoListDict

`TodoListDict` objects are dictionary-like objects that enable accessing todo lists.

```
class TodoListDict
    TodoListDict objects have the following property:
    default_list
        The ID of the default todo list.
```

TodoList

`TodoList` objects are dictionary-like objects that enable accessing todo lists.

```
class TodoList
    TodoList objects have the following properties:
    name
        The name of the todo list as a Unicode string.
    id
        Returns the ID of the todo list as an integer.
```

7.2.4 Repeat Rules

Repeat rules specify an entry's repeat status, that is, the recurrence of the entry. There are six repeat types:

- **daily**: repeated daily
- **weekly**: repeat on the specified days of the week, such as Monday and Wednesday, etc.
- **monthly_by_dates**: repeat monthly on the specified dates, such as the 15th and 17th day of the month
- **monthly_by_days**: repeat monthly on the specified days, such as the fourth Wednesday of the month, or the last Monday of the month
- **yearly_by_date**: repeat yearly on the specified date, such as December 24
- **yearly_by_day**: repeat yearly on the specified day, such as every third Tuesday of May

There are exceptions to repeat rules. For example, you can specify the datetime value (float) in such a way that the entry is not repeated on a specific day even if the repeat rule would specify otherwise.

You must set the start and end dates (floats) of the repeat. The end date can also be set to `None` to indicate that the repeating continues forever. You can set `interval` defining how often the repeat occurs, for example in a daily repeat: 1 means every day, 2 means every second day, etc. You can also set the `days` specifier which lets you explicitly specify the repeat days; for example in a weekly repeat you can set `"days": [0,2]` which sets the repeat to occur on Mondays and Wednesdays. If you do not set the `days` specifier, the repeat days are calculated automatically based on the start date.

You can modify repeat data by calling `rep_data = entry.get_repeat()`, then making changes to `rep_data` dictionary, and then calling `entry.set_repeat(rep_data)`.

Repeating can be cancelled by calling `entry.set_repeat` with a parameter that is interpreted to be false, such as `entry.set_repeat(None)`.

Repeat definition examples:

```

repeat = {"type":"daily", #repeat type
         "exceptions":[exception_day, exception_day+2*24*60*60],
         #no appointment on those days
         "start":appt_start_date, #start of the repeat
         "end":appt_start_date+30*24*60*60, #end of the repeat
         "interval":1} #interval (1=every day, 2=every second day etc.)

repeat = {"type":"weekly", #repeat type
         "days":[0,1], #which days in a week (Monday, Tuesday)
         "exceptions":[exception_day], #no appointment on that day
         "start":appt_start_date, #start of the repeat
         "end":appt_start_date+30*24*60*60, #end of the repeat
         "interval":1}
         #interval (1=every week, 2=every second week etc.)

repeat = {"type":"monthly_by_days", #repeat type
         # appointments on second Tuesday and last Monday of the month
         "days":[{"week":1, "day":1},{week":4, "day":0}],
         "exceptions":[exception_day], #no appointment on that day
         "start":appt_start_date, #start of the repeat
         "end":appt_start_date+30*24*60*60, #end of the repeat
         "interval":1}
         #interval (1=every month, 2=every second month etc.)

repeat = {"type":"monthly_by_dates", #repeat type
         "days":[0,15],
         # appointments on the 1st and 16th day of the month.
         "exceptions":[exception_day], #no appointment on that day
         "start":appt_start_date, #start of the repeat
         "end":appt_start_date+30*24*60*60, #end of the repeat
         "interval":1}
         #interval (1=every month, 2=every second month etc.)

repeat = {"type":"yearly_by_date", #repeat type
         "exceptions":[exception_day], #no appointment on that day
         "start":appt_start_date, #start of the repeat
         "end":appt_start_date+3*365*24*60*60, #end of the repeat
         "interval":1}
         #interval (1=every year, 2=every second year etc.)

repeat = {"type":"yearly_by_day", #repeat type
         # appointments on the second Tuesday of February
         "days":{"day":1, "week":1, "month":1},
         "exceptions":[exception_day], #no appointment on that day
         "start":appt_start_date, #start of the repeat
         "end":appt_start_date+3*365*24*60*60, #end of the repeat
         "interval":1}
         #interval (1=every year, 2=every second year etc.)

```

7.3 calendar for EKA2 — Access to calendar related services

The `calendar` module offers an API to calendar services. The `calendar` module represents a Symbian agenda database as a dictionary-like `CalendarDb` object, which contains `Entry` objects and which is indexed using the unique IDs of those objects. There are five types of entry objects: `AppointmentEntry`, `EventEntry`, `AnniversaryEntry`, `ReminderEntry`, and `TodoEntry`.

`CalendarDb` objects represent a live view into the database. If an entry is changed outside your Python application, the changes are visible immediately, and conversely any changes you commit into the database are visible immediately to other applications.

All time parameters use Unix time unless stated otherwise. For more information on Unix time, see Section 3.5, Date and Time.

7.3.1 Module Level Functions

The following free functions - functions that do not belong to any class - are defined in the `calendar` module:

`open([filename=None, mode=None])`

Opens a calendar database and returns a new `CalendarDb` object.

If `filename` is `None`, the default database is opened.

If `filename` is given, it should contain drive letter, colon and file's name, but no absolute path.

`mode` can be:

- `None`: Opens an existing calendar database.
- `'c'`: Opens an existing calendar database, or creates it if it doesn't exist.
- `'n'`: Creates a new, empty calendar database. If `filename` exists, the previous contents are erased.

7.3.2 CalendarDb Objects

Calendar entries are stored in a calendar database. There is one default calendar database but more calendar databases can be created by invoking `open` with parameters `'n'` or `'c'`.

`class CalendarDb`

`CalendarDb` objects have the following methods:

`add_appointment()`

Creates and returns a new appointment entry `AppointmentEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_event()`

Creates and returns a new event entry `EventEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_anniversary()`

Creates and returns a new anniversary entry `AnniversaryEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_todo()`

Creates and returns new todo entry `TodoEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`add_reminder()`

Creates and returns new reminder entry `ReminderEntry`. The entry is not added and saved into the database until `Entry.commit` is called.

`find_instances(start_date, end_date, search_str="u" [, appointments=0, events=0, anniversaries=0, todos=0, reminders=0])`

The parameters for this function include the start date, end date, search string, and optional parameters. The optional parameters define the entry types to be included into the search. By default all entry types are included. Returns a list that contains `Entry` instances found in the search. An instance is a dictionary that contains the entry ID and the datetime value. An entry may have several instances if it is repeated, for example once every week, etc.

`monthly_instances(month, appointments=0, events=0, anniversaries=0, todos=0, reminders=0)`

The parameters for this function include `month` (float) and optional parameters. The optional parameters define the entry types to be returned. Returns a list that contains entry instances occurring during the specified calendar month.

`daily_instances(day, appointments=0, events=0, anniversaries=0, todos=0)`
 The parameters for this function include *day* (float) and optional parameters. The optional parameters define the entry types to be returned. Returns a list that contains entry instances occurring on the specified day.

`export_vcalendars((int,...))`
 Returns a `vcalendar` string that contains the specified entries in vCalendar format. The parameter for this function is a tuple that contains the entry IDs of the exported entries.

`import_vcalendars(string)`
 Imports `vcalendar` entries, given in the string parameter, to the database. Returns a list that contains the unique IDs of the imported entries.

`__delitem__(id)`
 Deletes the given calendar `Entry` from the database. *id* is the unique ID of the calendar `Entry`.

`__getitem__(id)`
 Returns a calendar `Entry` object indicated by the unique ID. The returned object can be one of the following: `AppointmentEntry`, `EventEntry`, `AnniversaryEntry`, `ReminderEntry`, or `TodoEntry`. *id* is the unique ID of the calendar `Entry`.

7.3.3 Entry Objects

An `Entry` object represents a live view into the state of a single entry in the database. You can access the entries with an entry's unique ID. If you create a new entry using `db.add_appointment` etc., it is saved into the database only if you call the entry's `commit` method. In case an entry is already saved into the database, the autocommit mode is on by default and all the changes are automatically saved into the database, unless you call the entry's `begin` method. If you call the entry's `begin` method, the changes are not saved into the database until you call the entry's `commit` method.

Database entries cannot be locked. In other words, other applications are able to make changes to the database entries you are using (not directly to the `EntryObjects` you are using, but to their representation in the database) at the same time you are modifying them, even if you use `begin` and `commit` methods.

class `Entry`

`Entry` objects have the following methods and properties:

`content`

Sets or returns the entry's content text (Unicode).

`commit()`

Saves the entry or in case of a new entry adds the entry into the database. Note that this can be called only in case of a new entry, created with `db.add_appointment` etc., or after `begin` is called.

`rollback()`

Undoes the changes made after last `commit`.

`set_repeat(dictionary)`

Sets the repeat data of the entry. *dictionary* is a repeat data dictionary that contains all the repeat rules. For more information on repeat rules, see Section 7.3.4, Repeat Rules.

`get_repeat()`

Returns the repeat data dictionary of the entry.

`location`

Sets or returns the entry's location data (Unicode), for example meeting room information.

`set_time(start[, end])`

Sets the start and end datetime values of the entry (floats). If only one parameter is given, the other will have the same value.

In case of events, anniversaries, and todo entries the datetime values are truncated to corresponding date values.

`TodoEntries` can be made undated with `TodoEntry.set_time(None)`. Making the todo entry undated means removing the start and end date and all the repeat rules.

start_time
The start datetime value (float) of the entry or `None` if the start datetime of the entry is not set.

end_time
The end datetime value (float) of the entry or `None` if the end datetime of the entry is not set.

id
The unique ID of the entry.

last_modified
The datetime value (float) of the entry's last modification in universal time.

originating
An integer value indicating if the entry is an originating entry or a modifying entry.

alarm
The alarm datetime value (float) for the entry. `None` if `alarm` is not set. Alternatively removes the alarm if the value is set to `None`.

Alarms can be set to all `Entry` types. However, only alarms set to `Appointments` and `Anniversaries` will actually cause an alarm; this is similar to the Calendar application in your Nokia device, which allows you to set an alarm only for `Meetings` and `Anniversaries`. In addition, alarms set to any entries residing in a database other than the default database do not cause actual alarms either.

priority
The priority of the entry, which can be an integer ranging from 0 to 255. Native Phonebook and Calendar applications in Nokia devices use value 1 for high priority, 2 for normal priority, and 3 for low priority.

crossed_out
The crossed out value of an entry. Only valid for `todo` entries. A value that is interpreted as false means that the entry is not crossed out, whereas a value that is interpreted as true means that the entry is crossed out. Note that `TodoEntries` must also have a cross-out time. If `TodoEntry` is crossed out using this method, the moment of crossing out is set to the cross-out time of the `TodoEntry`. See also Section 7.3.3, `TodoEntry`, `cross_out_time`.

replication
Sets or returns the entry's replication status, which can be one of the following: `'open'`, `'private'`, or `'restricted'`.

as_vcalendar()
Returns this entry as a vCalendar string.

AppointmentEntry Objects

class AppointmentEntry

`AppointmentEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

EventEntry

class EventEntry

`EventEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

AnniversaryEntry

class AnniversaryEntry

`AnniversaryEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

ReminderEntry

`class ReminderEntry`

`ReminderEntry` class contains no additional methods compared to the `Entry` class from which it is derived.

TodoEntry

`TodoEntry` objects represent todo entry types. They have additional properties compared to the `Entry` class from which they are derived.

`class TodoEntry`

`TodoEntry` objects have the following additional properties:

`cross_out_time`

The cross-out date value of the entry. The value can be `None` meaning that the entry is not crossed out, or the cross-out date (float). The set value must be date (float). Setting a cross-out time also crosses out the entry. See also Section 7.3.3, Entry Object, `crossed_out`.

7.3.4 Repeat Rules

Repeat rules specify an entry's repeat status, that is, the recurrence of the entry. There are six repeat types:

- `daily`: repeated daily
- `weekly`: repeat on the specified days of the week, such as Monday and Wednesday, etc.
- `monthly_by_dates`: repeat monthly on the specified dates, such as the 15th and 17th day of the month
- `monthly_by_days`: repeat monthly on the specified days, such as the fourth Wednesday of the month, or the last Monday of the month
- `yearly_by_date`: repeat yearly on the specified date, such as December 24
- `yearly_by_day`: repeat yearly on the specified day, such as every third Tuesday of May

There are exceptions to repeat rules. For example, you can specify the datetime value (float) in such a way that the entry is not repeated on a specific day even if the repeat rule would specify otherwise.

You must set the start and end dates (floats) of the repeat. The end date can also be set to `None` to indicate that the repeating continues forever. You can set `interval` defining how often the repeat occurs, for example in a daily repeat: 1 means every day, 2 means every second day, etc. You can also set the `days` specifier which lets you explicitly specify the repeat days; for example in a weekly repeat you can set `"days": [0,2]` which sets the repeat to occur on Mondays and Wednesdays. If you do not set the `days` specifier, the repeat days are calculated automatically based on the start date.

You can modify repeat data by calling `rep_data = entry.get_repeat()`, then making changes to `rep_data` dictionary, and then calling `entry.set_repeat(rep_data)`.

Repeating can be cancelled by calling `entry.set_repeat` with a parameter that is interpreted to be false, such as `entry.set_repeat(None)`.

Repeat definition examples:

```
repeat = {"type": "daily", #repeat type
         "exceptions": [exception_day, exception_day+2*24*60*60],
         #no appointment on those days
         "start": appt_start_date, #start of the repeat
```

```

        "end":appt_start_date+30*24*60*60, #end of the repeat
        "interval":1} #interval (1=every day, 2=every second day etc.)

repeat = {"type":"weekly", #repeat type
        "days":[0,1], #which days in a week (Monday, Tuesday)
        "exceptions":[exception_day], #no appointment on that day
        "start":appt_start_date, #start of the repeat
        "end":appt_start_date+30*24*60*60, #end of the repeat
        "interval":1}
        #interval (1=every week, 2=every second week etc.)

repeat = {"type":"monthly_by_days", #repeat type
        # appointments on second Tuesday and last Monday of the month
        "days":[{"week":1, "day":1},{week":4, "day":0}],
        "exceptions":[exception_day], #no appointment on that day
        "start":appt_start_date, #start of the repeat
        "end":appt_start_date+30*24*60*60, #end of the repeat
        "interval":1}
        #interval (1=every month, 2=every second month etc.)

repeat = {"type":"monthly_by_dates", #repeat type
        "days":[0,15],
        # appointments on the 1st and 16th day of the month.
        "exceptions":[exception_day], #no appointment on that day
        "start":appt_start_date, #start of the repeat
        "end":appt_start_date+30*24*60*60, #end of the repeat
        "interval":1}
        #interval (1=every month, 2=every second month etc.)

repeat = {"type":"yearly_by_date", #repeat type
        "exceptions":[exception_day], #no appointment on that day
        "start":appt_start_date, #start of the repeat
        "end":appt_start_date+3*365*24*60*60, #end of the repeat
        "interval":1}
        #interval (1=every year, 2=every second year etc.)

repeat = {"type":"yearly_by_day", #repeat type
        # appointments on the second Tuesday of February
        "days":{"day":1, "week":1, "month":1},
        "exceptions":[exception_day], #no appointment on that day
        "start":appt_start_date, #start of the repeat
        "end":appt_start_date+3*365*24*60*60, #end of the repeat
        "interval":1}
        #interval (1=every year, 2=every second year etc.)

```

7.4 e32db — Interface to the Symbian native DB

The `e32db` module provides an API for relational database manipulation with a restricted SQL syntax. For details of DBMS support, see the S60 SDK documentation. For examples on using this module, see [6].

The `e32db` module defines the following functions:

`format_rawtime(timevalue)`

Formats *timevalue* (Symbian time) according to the current system's date/time formatting rules and returns it as a Unicode string.

`format_time(timevalue)`

Formats *timevalue* according to the current system's date/time formatting rules and returns it as a Unicode string.

7.4.1 Dbms Objects

class Dbms()

Creates a Dbms object. Dbms objects support basic operations on a database.

Dbms objects have the following methods:

begin()

Begins a transaction on the database.

close()

Closes the database object. It is safe to try to close a database object even if it is not open.

commit()

Commits the current transaction.

compact()

Compacts the database, reclaiming unused space in the database file.

create(*dbname*)

Creates a database with path *dbname*.

execute(*query*)

Executes an SQL *query*. On success, returns 0 if a DDL (SQL schema update) statement was executed. Returns the number of rows inserted, updated, or deleted, if a DML (SQL data update) statement was executed.

open(*dbname*)

Opens the database in file *dbname*. This should be a full Unicode path name, for example, `u'c:\\foo.db'`.

rollback()

Rolls back the current transaction.

7.4.2 DB_view Objects

class Db_view()

Creates a Db_view object. DB_view objects generate rowsets from a SQL query. They provide functions to parse and evaluate the rowsets.

Db_view objects have the following methods:

col(*column*)

Returns the value in *column*. The first column of the rowset has the index 1. If the type of the column is not supported, a **TypeError** is raised. See Table 7.1 for a list of supported data types.

col_count()

Returns the number of columns defined in the rowset.

col_length(*column*)

Gets the length of the value in *column*. Empty columns have a length of zero; non-empty numerical and date/time columns have a length of 1. For text columns, the length is the character count, and for binary columns, the length is the byte count.

col_raw(*column*)

Extracts the value of *column* as raw binary data, and returns it as a Python string. The first column of the rowset has the index 1. See Table 7.1 for a list of supported data types.

col_rawtime(*column*)

Extracts the value of a date/time column at index *column* as a long integer, which represents the raw Symbian time value. The first column of the rowset has the index 1. See Table 7.1 for a list of the supported data types.

col_type(*column*)

Returns the numeric type of the given column as an integer from a Symbian-specific list of types. This function is used in the implementation of method `col`.

`count_line()`
Returns the number of rows available in the rowset.

`first_line()`
Positions the cursor on the first row in the rowset.

`get_line()`
Gets the current row data for access.

`is_col_null(column)`
Tests whether *column* is empty. Empty columns can be accessed like normal columns. Empty numerical columns return a 0 or an equivalent value, and text and binary columns have a zero length.

`next_line()`
Moves the cursor to the next row in the rowset.

`prepare(db, query)`
Prepares the view object for evaluating an SQL select statement. *db* is a *Dbms* object and *query* the SQL query to be executed.

7.4.3 Mapping Between SQL and Python Data Types

See Table 7.1 for a summary of mapping between SQL and Python data types. The `col` function can extract any value except `LONG VARBINARY` and return it as the proper Python value. In addition, the `col_raw` function can extract any column type except `LONG VARCHAR` and `LONG VARBINARY` as raw binary data and return it as a Python string.

Inserting, updating, or searching for `BINARY`, `VARBINARY`, or `LONG VARBINARY` values is not supported. `BINARY` and `VARBINARY` values can be read with `col` or `col_raw`.

SQL type	Symbian column type (in the DBMS C++ API)	Python type	Supported
BIT	EDbColBit	int	yes
TINYINT	EDbColInt8		
UNSIGNED TINYINT	EDbColUInt8		
SMALLINT	EDbColInt16		
UNSIGNED SMALLINT	EDbColUInt16		
INTEGER	EDbColInt32		
UNSIGNED INTEGER	EDbColUInt32		
COUNTER	EDbColUInt32 (with the TDbCol::EAutoIncrement attribute)		
BIGINT	EDbColInt64	long	
REAL	EDbColReal32	float	
FLOAT	EDbColReal64		
DOUBLE			
DOUBLE PRECISION			
DATE	EDbColDateTime	float (or long, with <code>col_rawtime()</code>)	
TIME			
TIMESTAMP			
CHAR(<i>n</i>)	EDbColText	Unicode	
VARCHAR(<i>n</i>)			
LONG VARCHAR			
BINARY(<i>n</i>)	EDbColBinary	str	read only
VARBINARY(<i>n</i>)			
LONG VARBINARY	EDbColLongBinary	n/a	no

Table 7.1: Mapping between SQL and Python types

7.4.4 Date and Time Handling

The functions `col` and `format_time` use Unix time, seconds since January 1, 1970, 00:00:00 UTC, as the time format. Internally the database uses the native Symbian time representation that provides greater precision and range than the Unix time. The native Symbian time format is a 64-bit value that represents microseconds since January 1st 0 AD 00:00:00 local time, nominal Gregorian. BC dates are represented by negative values. Since converting this format to Unix time and back may cause slight round-off errors, you have to use the functions `col_rawtime` and `format_rawtime` if you need to be able to handle these values with full precision.

The representation of date and time literals in SQL statements depends on the current system date and time format. Note that the only accepted ordering of day, month, and year is the one that the system is currently configured to use. Dates in other order are rejected. The recommended way to form date/time literals for SQL statements is to use the functions `format_time` or `format_rawtime` that format the given date/time values properly according to the current system's date/time format settings.

7.5 e32dbm — DBM implemented using the Symbian native DBMS

The `e32dbm` module provides a DBM API that uses the native Symbian RDBMS as its storage back-end. The module API resembles that of the `gdbm` module. The main differences are:

- The `firstkey()` - `nextkey()` interface for iterating through keys is not supported. Use the "for key in db" idiom or the `keys` or `keysiter` methods instead.
- This module supports a more complete set of dictionary features than `gdbm`
- The values are always stored as Unicode, and thus the values returned are Unicode strings even if they were given to the DBM as normal strings.

7.5.1 Module Level Functions

The `e32dbm` defines the following functions:

`open(dbname[,flags, mode])`

Opens or creates the given database file and returns an `e32dbm` object. Note that `dbname` should be a full path name, for example, `u'c:\\foo.db'`. Flags can be:

- `'r'`: opens an existing database in read-only mode. This is the default value.
- `'w'`: opens an existing database in read-write mode.
- `'c'`: opens a database in read-write mode. Creates a new database if the database does not exist.
- `'n'`: creates a new empty database and opens it in read-write mode.

If the character `'f'` is appended to flags, the database is opened in *fast mode*. In fast mode, updates are written to the database only when one of these methods is called: `sync`, `close`, `reorganize`, or `clear`.

Since the connection object destructor calls `close`, it is not strictly necessary to close the database before exiting to ensure that data is saved, but it is still good practice to call the `close` method when you are done with using the database. Closing the database releases the lock on the file and allows the file to be reopened or deleted without exiting the interpreter.

If you plan to do several updates, it is highly recommended that you open the database in fast mode, since inserts and updates are more efficient when they are bundled together in a larger transaction. This is especially important when you plan to insert large amounts of data, since inserting records to `e32db` is very slow if done one record at a time.

7.5.2 e32dbm Objects

The `e32dbm` objects returned by the `open` function support most of the standard dictionary methods. The supported dictionary methods are:

- `__getitem__`
- `__setitem__`
- `__delitem__`
- `has_key`
- `update`
- `__len__`
- `__iter__`
- `iterkeys`
- `iteritems`
- `itervalues`
- `get`
- `setdefault`
- `pop`
- `popitem`
- `clear`

These work the same way as the corresponding methods in a normal dictionary.

In addition, `e32dbm` objects have the following methods:

`close()`

Closes the database. In fast mode, commits all pending updates to disk. `close` raises an exception if called on a database that is not open.

`reorganize()`

Reorganizes the database. Reorganization calls `compact` on the underlying `e32db` database file, which reclaims unused space in the file. Reorganizing the database is recommended after several updates.

`sync()`

In fast mode, commits all pending updates to disk.

Standard Library Support and Extensions

8.1 Support for Python Standard Library

The standard library support in Python for S60 is summarized in Table 8.1. For API descriptions, see [1].

Name	Type	Status	Remarks
<code>_testcapi</code>	PYD	Y	
<code>anydbm</code>	PY	X	DBM API is implemented by PY <code>e32dbm</code> that relies on PYD <code>e32db</code> (see Chapter 7.5, <code>e32dbm</code> Module)
<code>atexit</code>	PY	X	
<code>base64</code>	PY	X	
<code>bdb</code>	PY	(X)	
<code>binascii</code>	built-in	X	
<code>cmd</code>	PY	(X)	
<code>code</code>	PY	X	
<code>codecs</code>	PY	X	
<code>codeop</code>	PY	X	
<code>copy</code>	PY	X	
<code>copy_reg</code>	PY	X	
<code>cStringIO</code>	built-in	X	
<code>dis</code>	PY	(X)	
<code>errno</code>	built-in	X	
<code>exceptions</code>	built-in	X	
<code>__future__</code>	PY	X	
<code>httplib</code>	PY	X	
<code>imp</code>	built-in	X	
<code>keyword</code>	PY	X	
<code>linecache</code>	PY	X	
<code>marshal</code>	built-in	X	
<code>math</code>	built-in	X	
<code>md5</code> ¹	built-in	X	
<code>mimertools</code>	PY	X	
<code>operator</code>	built-in	X	
<code>os, os.path</code>	PY	X	Wraps built-in <code>e32posix</code> . Limitations discussed in Section 3.9, Limitations and Areas of Development.
<code>pdb</code>	PY	(X)	
<code>quopri</code>	PY	X	
Name	Type	Status	Remarks

¹Derived from the RSA Data Security, Inc. MD5 Message-Digest Algorithm.

<code>random</code>	PY	X	
<code>re</code>	PY	X	Uses PY <code>sre</code> as its engine.
<code>repr</code>	PY	X	
<code>rfc822</code>	PY	X	
<code>select</code>	PY	X	A minimal implementation: <code>select</code> is supported only for input from sockets.
<code>socket</code>	PY	X	Requires PYD <code>e32socket</code> . Contains extensions as described in Section 8.2.2, <code>socket</code> Module. Limitations discussed in Section 3.9, Limitations and Areas of Development.
<code>sre</code>	PY	X	Wraps built-in <code>_sre</code> .
<code>string</code>	PY	X	
<code>StringIO</code>	PY	X	
<code>struct</code>	built-in	X	
<code>sys</code>	built-in	X	
<code>thread</code>	built-in	X	Contains extensions as described in Section 8.2.1, <code>thread</code> Module
<code>threading</code>	PY	(X)	
<code>time</code>	built-in	X	
<code>traceback</code>	PY	X	
<code>types</code>	PY	X	
<code>urllib</code>	PY	X	
<code>urlparse(urlsplit only)</code>	PY	X	
<code>uu</code>	PY	X	
<code>warnings</code>	PY	X	
<code>whichdb</code>	PY	X	
<code>xreadlines</code>	built-in	X	
<code>zipfile</code>	PY	X	
<code>zlib</code>	PYD	X	

Table 8.1: Status of library module support.

Table 8.1 uses the following coding for module types:

- PY – module is implemented in Python.
- Built-in – module is a built-in C/C++ module.
- PYD – module is a dynamically loadable C/C++ module.

For support status, the following codes are used:

- X – included to the Series 60 Python distribution.
- (X) – not included to the Series 60 Python distribution, but works both on phone and SDK.
- Y – included only to the SDK distribution.

8.2 Extensions to Standard Library Modules

The following standard modules have been extended.

8.2.1 thread — S60 extensions to standard thread module

The following function has been added to the standard `thread` module:

`ao_waittid(thread_id)`

Synchronizes with the end of the execution of the thread identified by the given *thread_id*. The implementation is based on a Symbian OS active object. For the blocking behavior, see Section 4.1.2, `Ao_lock` Type.

8.2.2 socket — S60 extensions to standard socket module

Bluetooth (BT) support has been added to the standard `socket` module. The following related constants and functions are defined:

Note: In release 1.0 the functions `bt_advertise_service`, `bt_obex_receive`, and `bt_rfcomm_get_available_server_channel` incorrectly expected to be given the internal `e32socket.socket` object as the socket parameter instead of the proper `socket` object. Now the functions work correctly. The old calling convention is still supported but it is deprecated and may be removed in a future release.

`AF_BT`

Represents the Bluetooth address family.

`BTPROTO_RFCOMM`

This constant represents the Bluetooth protocol RFCOMM.

`RFCOMM`

`OBEX`

Bluetooth service classes supported by `bt_advertise_service`.

`AUTH`

`ENCRYPT`

`AUTHOR`

Bluetooth security mode flags.

`bt_advertise_service(name, socket, flag, class)`

Sets a service advertising the service *name* (Unicode) on local channel that is bound to *socket*. If *flag* is `True`, the advertising is turned on, otherwise it is turned off. The service class to be advertised is either `RFCOMM` or `OBEX`.

`bt_discover([address])`

Performs the Bluetooth device discovery (if the optional BT device address is not given) and the discovery of RFCOMM class services on the chosen device. Returns a pair: BT device address, dictionary of services, where Unicode service name is the key and the corresponding port is the value.

`bt_obex_discover([address])`

Same as `discover`, but for discovery of OBEX class services on the chosen device.

`bt_obex_send_file(address, channel, filename)`

Sends file *filename* (Unicode) wrapped into an OBEX object to remote *address*, *channel*.

`bt_obex_receive(socket, filename)`

Receives a file as an OBEX object, unwraps and stores it into *filename* (Unicode). *socket* is a bound OBEX socket.

`bt_rfcomm_get_available_server_channel(socket)`

Returns an available RFCOMM server channel for *socket*.

`set_security(socket, mode)`

Sets the security level of the given bound *socket*. The *mode* is an integer flag that is formed using a binary or operation of one or more of: `AUTH` (authentication), `ENCRYPT`, `AUTHOR` (authorization). Example: `set_security(s, AUTH | AUTHOR)`.

Note: When listening to a Bluetooth socket on the phone, it is necessary to set the security level.

Note: SSL is not supported in S60 1st Edition. SSL client certificates are not supported at all.

For examples on the usage of these functions, see Programming with Python for S60 Platform [6].

Setting default Access Point (AP) has been added to the standard `socket` module. The following related constants and functions are defined:

`select_access_point()`

This opens popup selection where access points are listed and can be selected. Returns selected access point id.

`access_point(apid)`

This creates access point object by given *apid*. Returns access point object.

`set_default_access_point(apo)`

This sets the default access point that is used when socket is opened. Setting *apo* to "None" will clear default access point.

`access_points()`

This lists access points id's and names that are available.

Example 1:

```
#access point is selected from the list
apid = select_access_point()
apo = access_point(apid)
set_default_access_point(apo)

s = socket(AF_INET, SOCK_STREAM)
print apo.ip()
s.connect(('www.sourceforge.net',80))
s.send('GET /\r\n\r\n')
s.recv(100)
s.close()
apo.stop()
```

Example 2:

```
#Access point id is already known
apo = access_point(1)
set_default_access_point(apo)

s = socket(AF_INET, SOCK_STREAM)
s.connect(('www.sourceforge.net',80))
s.send('GET /\r\n\r\n')
s.recv(100)
s.close()
apo.stop()
```

Example 3:

```
#display interface ip.
#access point is selected from the list
apid = select_access_point()
apo = access_point(apid)
apo.start()
#Note that ip-address is given by operator, if static ip-address is not defined,
#when connection is started
print apo.ip()
#When connection is closed dynamic ip-address is released
apo.stop()
```

Extending and Embedding

9.1 Python/C API Extensions

The native API exported by the interpreter in S60 environment consists of class `CSPyInterpreter`, Python/C API (see [3]) and a small set of extensions to Python/C API.

9.1.1 class `CSPyInterpreter`

The class `CSPyInterpreter` offers an interface for initializing the interpreter and for running scripts. It exports the following public interface:

```
static CSPyInterpreter*
NewInterpreterL(TBool aCloseStdlib = ETrue,
               void(*aStdioInitFunc)(void*) = NULL,
               void* aStdioInitCookie = NULL);
TInt RunScript(int argc, char** argv);
void PrintError();
void (*iStdI)(char* buf, int n);
void (*iStdO)(const char* buf, int n);
```

The caller of the constructor `CSPyInterpreter::NewInterpreterL()` may provide its own function *aStdioInitFunc* for initializing Symbian OS `STDLIB`'s standard I/O descriptors. It gets called with the argument *aStdioInitCookie*. The `CSPyInterpreter` class can also be requested to leave `STDLIB` open at its destruction.

The `RunScript` method establishes a Python interpreter context and runs the script file whose full path name is in `argv[0]` with the given argument vector. After completion, it leaves the interpreter context and returns a Symbian error code to indicate success or failure.

The `CSPyInterpreter::PrintError` method can be used to print current Python exception information to the standard error output.

9.1.2 Extensions to Python/C API

Defined in `symbian_python_ext_util.h`

```
PyObject* SPyErr_SetFromSymbianOSErr(int error)
```

Sets Python exception of type `PyExc_SymbianError` with the value field set to symbolic name of the Symbian OS enumeration value `error` and returns `NULL`. In case `error` has the special value `KErrPython`, it assumes that a Python exception has already been set and returns `NULL`.

The following functions can be used for storing the global data in a module implementation. They are thin wrappers around `PyDict_SetItem`, `PyDict_SetItemString`, `PyDict_GetItem`, `PyDict_GetItemString`, `PyDict_DelItem` and `PyDict_DelItemString`, respectively, and can be used in the same way. The data is stored in a special completely global dictionary shared by all modules and threads in the current interpreter.

```

int SPyAddGlobal(PyObject *key, PyObject *value)
int SPyAddGlobalString(char *key, PyObject *value)
PyObject* SPyGetGlobal(PyObject *key)
PyObject* SPyGetGlobalString(char *key)
void SPyRemoveGlobal(PyObject *key)
void SPyRemoveGlobalString(char *key)

```

Defined in `python_globals.h`

```

PyThreadState* PYTHON_TLS->thread_state
    Current thread state.

```

Thread state and interpreter lock management must be performed according to the instructions; see [3]. Python for S60 Platform extends the Python/C API by offering a facility for querying the related Python thread state (`PYTHON_TLS->thread_state`) from the context of the currently running thread. This can be used to re-establish the interpreter context with `PyEval_RestoreThread` in C/C++ code.

To save/restore the interpreter context:

```

Py_BEGIN_ALLOW_THREADS
/* ...your code... */
Py_END_ALLOW_THREADS

```

To restore/save the interpreter context:

```

PyEval_RestoreThread(PYTHON_TLS->thread_state)
/* ...your code... */
PyEval_SaveThread()

```

Defined in `pythread.h`

```

int PyThread_AtExit(void(*)())

```

An extension to the standard `thread` module's C API that can be used for registering thread-specific exit functions. In the main thread calling this function has the same effect as calling `Py_AtExit`. For more information, see [1].

9.2 Extending Python for S60

The general rules and guidelines for writing Python extensions apply in the S60 Python environment as well; for more information, see [2]. The Python/C API is available, see [3] In addition, for an example on porting a simple extension to S60, see [6].

The issues that need to be considered in the implementation of the extension modules include:

- Preparation of the data structures that make the C/C++ coded extensions visible to the Python interpreter and make it possible to perform calls from Python to C/C++ code
- Conversions between C/C++ representations of the Python objects and object types used in the extension code
- Maintenance of the reference counts of the C/C++ representations of the Python objects
- Passing of exceptions between C/C++ code and Python
- Management of interpreter's thread state and the interpreter lock

In addition to the concerns common for all Python C extensions, the following principles should be considered when implementing new Python interfaces in the S60 environment:

- Maximize the usage of Python's built-in types at the interfaces.
- Related to the above: design interfaces in such a way that information can be passed between them with minimal conversions.
- Convert Symbian operating system exceptions / errors to Python exceptions.
- Unicode strings are used at the interfaces to represent text that gets shown on the GUI. They can be passed to and from Symbian operating system without conversions.
- While performing potentially long-lasting / blocking calls from an extension implementation to services outside the interpreter, the interpreter lock must be released and then re-acquired after the call.
- Rather than always implementing a thin wrapper on top of a Symbian OS facility, consider the actual task for which the script writer needs the particular interface. For example, if the task involves interaction with the users using the GUI, the script writer's interest may well be limited to performing the interaction / information exchange in a way that is compatible with the UI style rather than having full control of the low-level details of the GUI implementation.
- The C/C++ implementation of a Python interface should be optimized for performance and covering access to the necessary features of the underlying Platform. Where necessary, the Python programming interface can be further refined by wrapper modules written in Python.

An extension module is packaged in its own dynamically loadable library that must be installed into `\system\libs` directory and named `'module_name.pyd'`. The module initialization function must be exported at ordinal 1. The module identification is based on the filename only. As a special feature of PyS60, an optional module finalizer function may be exported at ordinal 2.

The macro versions of memory-management functions `PyMem_MALLOC` and `PyObject_NEW` are not included. Use the functions `PyMem_Malloc` and `PyObject_New` instead.

9.2.1 Services for Extensions

S60 Python Platform implements an adaptation layer between S60 UI application framework and script language UI extensions to simplify UI extension development. This API is used by the implementation of the `appuifw` module but not exported in the current release. Some general utility services for extensions are also provided, see Chapter 9.1.

9.2.2 Example

This extension code snippet demonstrates some of the issues mentioned in this chapter, such as:

- Conversion from Python data types, usage of built-in data types at extension interface, usage of Unicode strings (lines 8-12)
- Maintenance of the reference counts (line 36)
- Passing of exceptions between C/C++ code and Python (line 34)
- Releasing the interpreter lock while performing a blocking call to a service outside the interpreter (lines 29, 31)
- Simplifying the API to the note facility of the Platform

```

01 extern "C" PyObject *
02 note(PyObject* /*self*/, PyObject *args)
03 {
04     TInt error = KErrNone;
05     int l_tx, l_ty;
06     char *b_tx, *b_ty;
07
08     if (!PyArg_ParseTuple(args, "u#s#", &b_tx, &l_tx, &b_ty, &l_ty))
09         return NULL;
10
11     TPtrC8 stype((TUint8*)b_ty, l_ty);
12     TPtrC note_text((TUint16 *)b_tx, l_tx);
13     CAknResourceNoteDialog* dlg = NULL;
14
15     if (stype.Compare(KErrorNoteType) == 0)
16         dlg = new CAknErrorNote(ETrue);
17     else if (stype.Compare(KInfoNoteType) == 0)
18         dlg = new CAknInformationNote(ETrue);
19     else if (stype.Compare(KConfNoteType) == 0)
20         dlg = new CAknConfirmationNote(ETrue);
21     else {
22         PyErr_BadArgument();
23         return NULL;
24     }
25
26     if (dlg == NULL)
27         return PyErr_NoMemory();
28
29     Py_BEGIN_ALLOW_THREADS
30     TRAP(error, dlg->ExecuteLD(note_text));
31     Py_END_ALLOW_THREADS
32
33     if (error != KErrNone)
34         return SPyErr_SetFromSymbianOSError(error);
35     else {
36         Py_INCREF(Py_None);
37         return Py_None;
38     }
39 }

```

Terms and Abbreviations

The following list defines the terms and abbreviations used in this document:

Term	Definition
AAC; Adaptive Audio Coding	AAC provides basically the same sound quality as MP3 while using a smaller bit rate. AAC is mainly used to compress music.
Advertise	Advertise service in Bluetooth makes it known that a certain Bluetooth service is available.
AMR	Adaptive Multi-rate Codec file format.
API	Application Programming Interface
Bluetooth	Bluetooth is a technology for wireless communication between devices that is based on a low-cost short-range radio link.
BPP	Bits Per Pixel
C STDLIB	Symbian OS's implementation of the C standard library
Dialog	A temporary user interface window for presenting context-specific information to the user, or prompting for information in a specific context.
Discovery	Discovery is a process where Bluetooth finds other nearby Bluetooth devices and their advertised services.
DLL	Dynamic link library
GSM; Global System for Mobile communication	GSM is a digital mobile telephone system that uses a variation of time division multiple access. It digitizes and compresses data, then sends it down a channel with two other streams of user data, each in its own time slot.
GUI	Graphical User Interface
I/O	input/output
IP	Internet Protocol
MBM; Multi-BitMap	The native Symbian OS format used for pictures. MBM files can be generated with the <code>bmconv.exe</code> tool included in the S60 SDK.
MIDI; Musical Instrument Digital Interface	A protocol and a set of commands for storing and transmitting information about music.
MIF; Multi-Image File	MIF files are similar to MBM files and can contain compressed SVG-T files. This file type can be generated with the <code>MifConv.exe</code> tool.
MIME; Multi-purpose Internet Mail Extensions	MIME is an extension of the original Internet e-mail protocol that can be used to exchange different kinds of data files on the Internet.
MP3	A standard technology and format for compressing a sound sequence into a very small file while preserving the original level of sound quality when it is played.
OS	Operating System
Real Audio	An audio format developed by Real Networks.
RDBMS	Relational database management system
SMS; Short Message System (within GSM)	SMS is a service for sending messages of up to 160 characters, or 224 characters if using a 5-bit mode, to mobile phones that use GSM communication.

Term	Definition
Softkey	Softkey is a key that does not have a fixed function nor a function label printed on it. On a phone, selection keys reside below or above on the side of the screen, and derive their meaning from what is presently on the screen.
SQL	Structured Query Language
SVG, SVG-T; Scalable Vector Graphics (-Tiny)	XML-based vector graphics format for describing two-dimensional graphics and graphical applications.
Twip	Twips are screen-independent units to ensure that the proportion of screen elements are the same on all display systems. A twip is defined as 1/1440 of an inch, or 1/567 of a centimeter.
UI	User Interface
UI control	UI control is a GUI component that enables user interaction and represents properties or operations of an object.
WAV	A file format for recording sound, especially in multimedia applications.

BIBLIOGRAPHY

- [1] G. van Rossum, and F.L. Drake, Jr., editor. [Python] Library Reference. Available at <http://www.python.org/doc>
- [2] G. van Rossum, and F.L. Drake, Jr., editor. Extending and Embedding [the Python Interpreter]. Available at <http://www.python.org/doc>
- [3] G. van Rossum, and F.L. Drake, Jr., editor. Python/C API [Reference Manual]. Available at <http://www.python.org/doc>
- [4] S60 SDK documentation, available at <http://www.forum.nokia.com/>
- [5] Getting Started with Python for S60 Platform, available at <http://www.forum.nokia.com/>
- [6] Programming with Python for S60 Platform, available at <http://www.forum.nokia.com/>
- [7] Audio & Video section on the *Forum Nokia* Web site (for Nokia devices), <http://www.forum.nokia.com/audiovideo>
- [8] Developers section on the *S60 Platform* Web site (for all S60 devices), <http://www.s60.com/>
- [9] Python for S60 developer discussion board <http://discussion.forum.nokia.com/>
- [10] Scalable Vector Graphics (SVG) 1.1 Specification <http://www.w3.org/TR/SVG/>

Reporting Bugs

In order to improve the quality of Python for S60 the developers would like to know of any deficiencies you find in Python for S60 or its documentation.

Before submitting a report, you will be required to log into SourceForge; this will make it possible for the developers to contact you for additional information if needed. It is not possible to submit a bug report anonymously.

All bug reports should be submitted via the project PyS60 Bug Tracker on SourceForge (http://sourceforge.net/tracker/?group_id=154155). The bug tracker offers a Web form which allows pertinent information to be entered and submitted to the developers.

The first step in filing a report is to determine whether the problem has already been reported. The advantage in doing so, aside from saving the developers time, is that you learn what has been done to fix it; it may be that the problem has already been fixed for the next release, or additional information is needed (in which case you are welcome to provide it if you can!). To do this, search the bug database using the search box near the bottom of the page.

If the problem you're reporting is not already in the bug tracker, go back to the project PyS60 Bug Tracker (http://sourceforge.net/tracker/?group_id=154155). Select the "Submit a Bug" link at the top of the page to open the bug reporting form.

The submission form has a number of fields. The only fields that are required are the "Summary" and "Details" fields. For the summary, enter a *very* short description of the problem; less than ten words is good. In the Details field, describe the problem in detail, including what you expected to happen and what did happen. Be sure to include the version of Python for S60 you used, whether any extension modules were involved and what hardware (the S60 device model or emulator) you were using, including version information of the S60 SDK and your device firmware version as appropriate. You can see the device firmware version by entering `*#0000#` on the device keypad - please include all information that is shown by this code.

The only other field that you may want to set is the "Category" field, which allows you to place the bug report into a broad category (such as "Documentation" or "Library").

Each bug report will be assigned to a developer who will determine what needs to be done to correct the problem. You will receive an update each time action is taken on the bug.

See Also:

How to Report Bugs Effectively

(<http://www-mice.cs.ucl.ac.uk/multimedia/software/documentation/ReportingBugs.html>)

Article which goes into some detail about how to create a useful bug report. This describes what kind of information is useful and why it is useful.

Bug Writing Guidelines

(<http://www.mozilla.org/quality/bug-writing-guidelines.html>)

Information about writing a good bug report. Some of this is specific to the Mozilla project, but describes general good practices.

MODULE INDEX

A

appuifw, 13
audio, 47

C

calendar, 60, 65
camera, 33
contacts, 55

E

e32, 9
e32db, 70
e32dbm, 73

G

glcanvas, 44
gles, 38
graphics, 27

I

inbox, 50

K

keycapture, 35

L

location, 51

M

messaging, 49

P

position, 52

S

socket, 77
sysinfo, 11

T

telephone, 49
thread, 77
topwindow, 36

INDEX

Symbols

`__delitem__()` (CalendarDb method), 61, 67
`__delitem__()` (ContactDb method), 56
`__delitem__()` (Contact method), 58
`__getitem__()` (CalendarDb method), 61, 67
`__getitem__()` (array method), 38
`__len__()` (array method), 38
`__setitem__()` (array method), 38

A

`access_point()` (in module socket), 78
`access_points()` (in module socket), 78
`activate_tab()` (Application method), 18
`active_profile()` (in module sysinfo), 11
`add()` (Text method), 22
`add_anniversary()` (CalendarDb method), 61, 66
`add_appointment()` (CalendarDb method), 61, 66
`add_contact()` (ContactDb method), 55
`add_event()` (CalendarDb method), 61, 66
`add_field()` (Contact method), 57
`add_group()` (Groups method), 59
`add_image()` (TopWindow method), 36
`add_reminder()` (CalendarDb method), 66
`add_todo()` (CalendarDb method), 61, 66
`add_todo_list()` (CalendarDb method), 61
`address()` (Inbox method), 50
AF_BT (data in socket), 77
`after()` (Ao_timer method), 11
alarm (Entry attribute), 63, 68
all_keys (data in keycapture), 35
AnniversaryEntry (class in calendar), 63, 68
`ao_callgate()` (in module e32), 9
Ao_lock (class in e32), 10
`ao_sleep()` (in module e32), 9
Ao_timer (class in e32), 11
`ao_waittid()` (in module thread), 77
`ao_yield()` (in module e32), 9
Application (class in appuifw), 16
AppointmentEntry (class in calendar), 63, 68
appuifw (standard module), 13
`arc()` (method), 32
array (class in gles), 38
`as_vcalendar()` (Entry method), 63, 68
`as_vcard()` (Contact method), 57
audio (extension module), 47

AUTH (data in socket), 77
AUTHOR (data in socket), 77
`available_fonts()` (in module appuifw), 15

B

`background_color` (TopWindow attribute), 37
`battery()` (in module sysinfo), 11
`begin()`
 Contact method, 56
 Dbms method, 71
`bind()`
 GLCanvas method, 45
 Inbox method, 51
 Listbox method, 23
 Text method, 22
`blit()` (method), 32
body (Application attribute), 16
`bt_advertise_service()` (in module socket), 77
`bt_discover()` (in module socket), 77
`bt_obex_discover()` (in module socket), 77
`bt_obex_receive()` (in module socket), 77
`bt_obex_send_file()` (in module socket), 77
`bt_rfcomm_get_available_server_channel()`
 (in module socket), 77
BTPROTO_RFCOMM (data in socket), 77

C

calendar (extension module), 60, 65
CalendarDb (class in calendar), 61, 66
camera (extension module), 33
`cameras_available()` (in module camera), 33
`cancel()` (Ao_timer method), 11
Canvas (class in appuifw), 25
`clear()`
 method, 32
 Text method, 22
`close()`
 Dbms method, 71
 e32dbm method, 74
 Sound method, 48
`col()` (Db_view method), 71
`col_count()` (Db_view method), 71
`col_length()` (Db_view method), 71
`col_raw()` (Db_view method), 71
`col_rawtime()` (Db_view method), 71
`col_type()` (Db_view method), 71

color (Text attribute), 20
 commit()
 Contact method, 56
 Dbms method, 71
 Entry method, 62, 67
 compact()
 CalendarDb method, 62
 ContactDb method, 56
 Dbms method, 71
 compact_required() (ContactDb method), 56
 Contact (class in contacts), 56
 ContactDb (class in contacts), 55
 ContactField (class in contacts), 59
 contacts (extension module), **55**
 content() (Inbox method), 50
 content (Entry attribute), 62, 67
 Content_handler (class in appuifw), 24
 corner_type (TopWindow attribute), 37
 count_line() (Db_view method), 72
 create() (Dbms method), 71
 cross_out_time (TodoEntry attribute), 63, 69
 crossed_out (Entry attribute), 63, 68
 current() (Listbox method), 24
 current_position() (Sound method), 49
 current_volume() (Sound method), 48

D

daily_instances() (CalendarDb method), 61, 67
 Db_view (class in e32db), 71
 Dbms (class in e32db), 71
 default_list (TodoListDict attribute), 64
 default_module() (in module position), 52
 delete()
 Inbox method, 51
 Text method, 22
 dial() (in module telephone), 49
 display_pixels() (in module sysinfo), 11
 display_twips() (in module sysinfo), 11
 drawNow() (GLCanvas method), 45
 drive_list() (in module e32), 9
 duration() (Sound method), 48

E

e32 (extension module), **9**
 e32db (extension module), **70**
 e32dbm (module), **73**
 EAColumn (data in appuifw), 19
 EApplicationWindow (data in appuifw), 18
 EBatteryPane (data in appuifw), 18
 EBColumn (data in appuifw), 19
 ECColumn (data in appuifw), 19
 EContextPane (data in appuifw), 18
 EControlPane (data in appuifw), 18
 EControlPaneBottom (data in appuifw), 19
 EControlPaneTop (data in appuifw), 19
 ECreated (data in messaging), 49
 EDColumn (data in appuifw), 19
 EDeleted (data in messaging), 49

EFatalServerError (data in messaging), 50
 EFindPane (data in appuifw), 19
 EIndicatorPane (data in appuifw), 19
 ellipse() (method), 32
 EMainPane (data in appuifw), 18
 EMovedToOutBox (data in messaging), 49
 ENaviPane (data in appuifw), 19
 ENCRYPT (data in socket), 77
 end_time (Entry attribute), 62, 68
 ENoServiceCentre (data in messaging), 50
 ENotReady (data in audio), 47
 Entry (class in calendar), 62, 67
 EOpen (data in audio), 47
 EPlaying (data in audio), 47
 ERecording (data in audio), 47
 EScheduledForSend (data in messaging), 49
 EScheduleFailed (data in messaging), 50
 EScreen (data in appuifw), 18
 ESendFailed (data in messaging), 50
 ESent (data in messaging), 49
 ESignalPane (data in appuifw), 18
 EStaconBottom (data in appuifw), 19
 EStaconTop (data in appuifw), 19
 EStatusPane (data in appuifw), 18
 EStatusPaneBottom (data in appuifw), 19
 EStatusPaneTop (data in appuifw), 19
 ETitlePane (data in appuifw), 18
 EUniversalIndicatorPane (data in appuifw), 19
 EventEntry (class in calendar), 63, 68
 EWallpaperPane (data in appuifw), 19
 execute()
 Dbms method, 71
 Form method, 20
 exit_key_handler (Application attribute), 17
 export_vcalendars() (CalendarDb method), 61, 67
 export_vcards() (ContactDb method), 56
 exposure_modes() (in module camera), 33

F

FFormAutoFormEdit (data in appuifw), 20
 FFormAutoLabelEdit (data in appuifw), 20
 FFormDoubleSpaced (data in appuifw), 20
 FFormEditModeOnly (data in appuifw), 20
 FFormViewModeOnly (data in appuifw), 20
 field_types() (ContactDb method), 56
 file_copy() (in module e32), 9
 find()
 Contact method, 58
 ContactDb method, 56
 find_instances() (CalendarDb method), 61, 66
 first_line() (Db_view method), 72
 flags (Form attribute), 20
 flash_modes() (in module camera), 33
 focus
 Application attribute, 17
 Text attribute, 21
 font (Text attribute), 21

Form (class in appuifw), 19
format_rawtime() (in module e32db), 70
format_time() (in module e32db), 70
forwarding (KeyCatcher attribute), 36
free_drivespace() (in module sysinfo), 11
free_ram() (in module sysinfo), 12
full_name() (Application method), 18

G

get() (Text method), 22
get_line() (Db_view method), 72
get_pos() (Text method), 22
get_repeat() (Entry method), 62, 67
glBufferData() (in module gles), 42
glBufferDatab() (in module gles), 42
glBufferDataf() (in module gles), 42
glBufferDatab() (in module gles), 42
glBufferDataub() (in module gles), 42
glBufferDataus() (in module gles), 42
glBufferDataax() (in module gles), 42
glBufferSubData() (in module gles), 42
glBufferSubDatab() (in module gles), 42
glBufferSubDataf() (in module gles), 42
glBufferSubDatab() (in module gles), 42
glBufferSubDataub() (in module gles), 42
glBufferSubDataus() (in module gles), 42
glBufferSubDataax() (in module gles), 42
GLCanvas (class in glcanvas), 45
glcanvas (extension module), **44**
glClipPlanef() (in module gles), 42
glClipPlanex() (in module gles), 43
glColorPointer() (in module gles), 39
glColorPointerf() (in module gles), 39
glColorPointerub() (in module gles), 39
glColorPointerx() (in module gles), 39
glCompressedTexImage2D() (in module gles), 39
glCompressedTexSubImage2D() (in module gles),
39
glDeleteBuffers() (in module gles), 43
glDeleteTextures() (in module gles), 39
glDrawElements() (in module gles), 39
glDrawElementsub() (in module gles), 39
glDrawElementsus() (in module gles), 39
glDrawTexfvOES() (in module gles), 43
glDrawTexivOES() (in module gles), 43
glDrawTexsvOES() (in module gles), 43
gles (extension module), **38**
glFogv() (in module gles), 39
glFogxv() (in module gles), 39
glGenBuffers() (in module gles), 43
glGenTextures() (in module gles), 39
glGetBooleanv() (in module gles), 43
glGetBufferParameteriv() (in module gles), 43
glGetClipPlanef() (in module gles), 43
glGetFixedv() (in module gles), 43
glGetFloatv() (in module gles), 43
glGetIntegerv() (in module gles), 39
glGetLightfv() (in module gles), 43

glGetLightxv() (in module gles), 43
glGetMaterialfv() (in module gles), 43
glGetMaterialxv() (in module gles), 43
glGetString() (in module gles), 39
glGetTexEnvf() (in module gles), 43
glGetTexEnvx() (in module gles), 43
glGetTexParameterf() (in module gles), 43
glGetTexParameterx() (in module gles), 43
glLightfv() (in module gles), 40
glLightModelfv() (in module gles), 39
glLightModelxv() (in module gles), 40
glLightxv() (in module gles), 40
glLoadMatrixf() (in module gles), 40
glLoadMatrixx() (in module gles), 40
glMaterialfv() (in module gles), 40
glMaterialxv() (in module gles), 40
glMatrixIndexPointerOES() (in module gles), 43
glMatrixIndexPointerOESub() (in module gles),
43
glMultMatrixf() (in module gles), 40
glMultMatrixx() (in module gles), 40
glNormalPointer() (in module gles), 40
glNormalPointerb() (in module gles), 40
glNormalPointerf() (in module gles), 40
glNormalPointers() (in module gles), 40
glNormalPointerx() (in module gles), 40
glPointParameterfv() (in module gles), 44
glPointParameterxv() (in module gles), 44
glPointSizePointerOES() (in module gles), 44
glPointSizePointerOESf() (in module gles), 44
glPointSizePointerOESx() (in module gles), 44
glReadPixels() (in module gles), 40
glTexCoordPointer() (in module gles), 40
glTexCoordPointerb() (in module gles), 40
glTexCoordPointerf() (in module gles), 41
glTexCoordPointers() (in module gles), 40
glTexCoordPointerx() (in module gles), 41
glTexEnvfv() (in module gles), 41
glTexEnvxv() (in module gles), 41
glTexImage2D() (in module gles), 41
glTexSubImage2D() (in module gles), 41
glVertexPointer() (in module gles), 41
glVertexPointerb() (in module gles), 41
glVertexPointerf() (in module gles), 41
glVertexPointers() (in module gles), 41
glVertexPointerx() (in module gles), 41
glWeightPointerOES() (in module gles), 44
glWeightPointerOESf() (in module gles), 44
glWeightPointerOESx() (in module gles), 44
graphics (extension module), **27**
Group (class in contacts), 59
Groups (class in contacts), 59
groups (ContactDb attribute), 56
gsm_location() (in module location), 51

H

hang_up() (in module telephone), 49
hide() (TopWindow method), 36

highlight_color (Text attribute), 21
HIGHLIGHT_ROUNDED (data in appuifw), 22
HIGHLIGHT_SHADOW (data in appuifw), 22
HIGHLIGHT_STANDARD (data in appuifw), 22

I

Icon (class in appuifw), 24
id
 Contact attribute, 56
 Entry attribute, 62, 68
 Group attribute, 59
 ToDoList attribute, 64
Image.inspect() (in module graphics), 27
Image.new() (in module graphics), 27
Image.open() (in module graphics), 27
image_modes() (in module camera), 33
image_sizes() (in module camera), 33
images (TopWindow attribute), 37
imei() (in module sysinfo), 11
import_vcalendars() (CalendarDb method), 61, 67
import_vcards() (ContactDb method), 56
in_emulator() (in module e32), 9
inactivity() (in module e32), 10
Inbox (class in inbox), 50
inbox (extension module), **50**
insert() (Form method), 20
is_col_null() (Db_view method), 72
is_group (Contact attribute), 56
is_ui_thread() (in module e32), 10

K

keycapture (extension module), **35**
keys() (ContactDb method), 56
keys (KeyCatcher attribute), 35
KMdaRepeatForever (data in audio), 47

L

label (ContactField attribute), 59
last_key() (KeyCatcher method), 36
last_modified (Entry attribute), 62, 68
layout() (Application method), 18
len() (Text method), 22
length() (Form method), 20
line() (method), 31
Listbox (class in appuifw), 23
load() (Image method), 28
location
 ContactField attribute, 59
 Entry attribute, 62, 67
 extension module, **51**

M

makeCurrent() (GLCanvas method), 45
max_ramdrive_size() (in module sysinfo), 12
max_volume() (Sound method), 48
max_zoom() (in module camera), 33
maximum_size (TopWindow attribute), 37

measure_text() (method), 32
menu
 Application attribute, 17
 Form attribute, 20
messaging (extension module), **49**
mms_send() (in module messaging), 49
module_info() (in module position), 52
modules() (in module position), 52
monthly_instances() (CalendarDb method), 61, 66
multi_query() (in module appuifw), 16
multi_selection_list() (in module appuifw), 16

N

name
 Group attribute, 59
 ToDoList attribute, 64
next_line() (Db_view method), 72
note() (in module appuifw), 16

O

OBEX (data in socket), 77
open()
 Content_handler method, 24
 Dbms method, 71
 in module calendar, 60, 66
 in module contacts, 55
 in module e32dbm, 73
open_standalone() (Content_handler method), 24
originating (Entry attribute), 68
os_version() (in module sysinfo), 12

P

pieslice() (method), 32
play() (Sound method), 47
point() (method), 32
polygon() (method), 31
pop() (Form method), 20
popup_menu() (in module appuifw), 16
position() (in module position), 52
position
 extension module, **52**
 TopWindow attribute, 37
prepare() (Db_view method), 72
priority (Entry attribute), 63, 68
pys60_version (data in e32), 9
pys60_version_info (data in e32), 9
PYTHON_TLS->thread_state, 80
PyThread_AtExit(), 80

Q

query() (in module appuifw), 15

R

record() (Sound method), 48
rectangle() (method), 32

release() (in module camera), 35
 ReminderEntry (class in calendar), 69
 remove_image() (TopWindow method), 36
 reorganize() (e32dbm method), 74
 replication (Entry attribute), 63, 68
 reset_inactivity() (in module e32), 10
 resize() (Image method), 28
 RFCOMM (data in socket), 77
 ring_type() (in module sysinfo), 12
 rollback()
 Contact method, 57
 Dbms method, 71
 Entry method, 62, 67

S

s60_version_info (data in e32), 10
 save() (Image method), 28
 save_hook (Form attribute), 20
 say() (in module audio), 47
 schema (ContactField attribute), 59
 screen (Application attribute), 17
 screenshot() (in module graphics), 27
 select_access_point() (in module socket), 78
 select_module() (in module position), 52
 selection_list() (in module appuifw), 16
 set() (Text method), 23
 set_default_access_point() (in module socket), 78
 set_exit() (Application method), 18
 set_home_time() (in module e32), 9
 set_list() (Listbox method), 24
 set_pos() (Text method), 23
 set_position() (Sound method), 48
 set_repeat() (Entry method), 62, 67
 set_requestors() (in module position), 52
 set_security() (in module socket), 77
 set_tabs() (Application method), 18
 set_time() (Entry method), 62, 67
 set_volume() (Sound method), 48
 shadow (TopWindow attribute), 37
 show() (TopWindow method), 36
 signal() (Ao_lock method), 11
 signalBars() (in module sysinfo), 12
 signal_dbm() (in module sysinfo), 12
 size
 Canvas attribute, 25
 Image attribute, 29
 TopWindow attribute, 37
 sms_messages() (Inbox method), 50
 sms_send() (in module messaging), 49
 socket (extension module), **77**
 Sound (class in audio), 47
 Sound.open() (in module audio), 47
 SPyAddGlobal(), 80
 SPyAddGlobalString(), 80
 SPyErr_SetFromSymbianOSError(), 79
 SPyGetGlobal(), 80
 SPyGetGlobalString(), 80

SPyRemoveGlobal(), 80
 SPyRemoveGlobalString(), 80
 start() (KeyCaptor method), 36
 start_exe() (in module e32), 10
 start_finder() (in module camera), 35
 start_server() (in module e32), 10
 start_time (Entry attribute), 62, 68
 state() (Sound method), 48
 stop()
 Image method, 29
 KeyCaptor method, 36
 Sound method, 48
 stop_finder() (in module camera), 35
 style (Text attribute), 21
 STYLE_BOLD (data in appuifw), 21
 STYLE_ITALIC (data in appuifw), 22
 STYLE_STRIKETHROUGH (data in appuifw), 22
 STYLE_UNDERLINE (data in appuifw), 22
 sw_version() (in module sysinfo), 12
 sync() (e32dbm method), 74
 sysinfo (extension module), **11**

T

take_photo() (in module camera), 33
 telephone (extension module), **49**
 text() (method), 32
 thread (extension module), **77**
 time() (Inbox method), 50
 title
 Application attribute, 17
 Contact attribute, 56
 todo_list (TodoEntry attribute), 64
 todo_lists (CalendarDb attribute), 61
 TodoEntry (class in calendar), 63, 69
 TodoList (class in calendar), 64
 TodoListDict (class in calendar), 64
 TopWindow (class in topwindow), 36
 topwindow (extension module), **36**
 total_ram() (in module sysinfo), 12
 total_rom() (in module sysinfo), 12
 transpose() (Image method), 28
 type (ContactField attribute), 59

U

uid() (Application method), 18
 unread() (Inbox method), 51

V

value (ContactField attribute), 59
 visible (TopWindow attribute), 37

W

wait() (Ao_lock method), 10
 white_balance_modes() (in module camera), 33